

ERTEC WESTERN INC LONG BEACH CA F/8 8/7 MX SITING INVESTIGATION, GEOTECHNICAL EVALUATION, DETAILED AGGR--ETC(U) JUN 81 F04704-80-C-0006 AD-A112 688 UNCLASSIFIED E-TR-47-PA NL

# AD 2688

を持ちなおけるか



MICROCOPY RESOLUTION TEST CHART ...



A Commence of the Commence of

# MX SITING INVESTIGATION GEOTECHNICAL EVALUATION

# DETAILED AGGREGATE RESOURCES STUDY PAHROC STUDY AREA, NEVADA

## Prepared for:

U.S. Department of the Air Force Ballistic Missile Office Norton Air Force Base, California 92409

Prepared by:

Ertec Western, Inc. 3777 Long Beach Boulevard Long Beach, California 90807

	PHO	TOGRAPH THIS	SHEET
8	LEVEL		INVENTORY
AD-A11268	LEVEL	COCUMENT IDENTI	7-PA- FICATION
AD-1	This d	ocument has been bild release and s ution is unlimited	cale; its
<del></del>	<u></u>	DISTRIBUTIO	N STATEMENT
ACCESSION FOR NTIS GRAAD DTIC TAB UNANNOUNCED JUSTIFICATION  BY DISTRIBUTION /		COPY INSPECTED	MAR 2 6 1982
AVAILABILITY CODES  DIST  AVAILABILITY CODES  *Original contains color  plates: All DIAC reproducts  ions will be in black and  white*			
		03 13	
DATE RECEIVED IN DTIC PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDA-2			
DTIC FORM 70/	Δ		DOCUMENT PROCESSING SHEE

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)		
REPORT DOCUMENTATION PAGE	READ INSTRUCTIONS BEFORE COMPLETING FORM	
	. 3. RECIPIENT'S CATALOG NUMBER	
E-TR-47 - PA  4. TITLE (and Subtitle)		
1 autiliar Anneariste Pesitaries	5. TYPE OF REPORT & PERIOD COVE 4ED	
Study - Pohroc Study Are a	6. PERFORMING ORG. REPORT NUMBER	
7. AUTHOR(s)	B. CONTRACT OR GRANT NUMBER()	
Ertec Western, Inc.	FU4704-80-C-COL	
9. PERFORMING ORGANIZATION NAME AND ADDRESS	10. PROGRAM ELEMENT, PROJECT, 'ASK AREA & WORK UNIT NUMBERS	
Entre Worten Toolframents Togre Mounds	64312 F	
11 CONTROLLING OFFICE NAME AND ADDRESS	12. REPORT DATE	
Supple Some of the System of the second of the Supple Supp	5 Jun 8/	
No. 401 2015 (0.99809 (5A.2780)	13. NUMBER OF PAGES	
14. MONITORING AGENCY NAME & ADDRESS(II dillerent from Controlling Office)	15. SECURITY CLASS, (of this report)	
	ISO. DECLASSIFICATION DOWNGRA. ING	
16. DISTRIBUTION STATEMENT (of this Report)		
Destination of all of the	•	
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different to	om Report)	
pistribution Colimited		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number	ton and	
19. KEY WORDS (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block number 5000 (Continue on reverse side il necessary and identity by block	ize, tranch logs,	
caliche	•	
20. ABSTRACT (Continue on reverse side it necessary and identify by block number Detailed aggregate resources study, Pahroc	twa, Nevada, Report	
contains analysis, evaluation and quantity of ag	e Dahraman Nalla	
in the Pahroc Valley and the nexthern porter Class RBIA, RBIb and RBII aggregates for	Paris la ser Clare	
I CHAS KIDIA, RBIG and KIBIT addictions to	LORD BASE, CIASS	
CAI, CAZ, CB, CCI and CCZ aggregate for source.		

#### **FOREWORD**

This report is one of a series prepared for the Department of the Air Force, Ballistic Missile Office (BMO), in compliance with Contract No. F04704-80-C-0006, CDRL Item No. 004A2. These reports present the results of Detailed Aggregate Resources Studies (DARS) within and adjacent to selected areas in Nevada and Utah that are under consideration for siting the MX missile system.

This volume contains the results of the aggregate resources evaluation for the Pahroc study area. Results of this report are presented as text, appendices, and three drawings. This report has been prepared and submitted on the assumption that the reader is familiar with previous aggregate resources reports.

. .. ..

# TABLE OF CONTENTS

2.1 Physiography				Page
1.0 INTRODUCTION 1 1.1 Study Area 1 1.2 Background 1 1.3 Objectives 6 1.4 Scope 6 2.0 GEOLOGIC SETTING 8 2.1 Physiography	FOREW	ORD .		i
1.1 Study Area	EXECU:	rive :	SUMMARY	v
1.2 Background 1.3 Objectives 6 1.4 Scope 6 2.0 GEOLOGIC SETTING 8  2.1 Physiography 8 2.2 Location and Description of Geologic Units 8 2.2.1 Rock Units 9 2.2.2 Basin-Fill Units 9 2.2.2 Basin-Fill Units 9 3.0 ROAD-BASE AGGREGATES EVALUATION 12  3.1 Study Approach 12 3.1.1 Requirements for Road-Base Aggregates 12 3.1.2 Data Acquisition and Analysis 13 3.1.3 Presentation of Results 15 3.1.4 Classification of Road-Base Aggregates 17 3.2 Sources of Road-Base Aggregates 19 3.2.1 Basin-Fill Sources 19 3.2.2 Rock Sources 19 3.2.2 Rock Sources 24  4.0 CONCRETE AGGREGATES EVALUATION 26 4.1 Study Approach 26 4.1.1 Requirements for Concrete Aggregates 26 4.1.2 Data Acquisition and Analysis 28 4.1.3 Presentation of Results 34 4.1.4 Classification of Concrete Aggregates 36 4.2 Sources of Concrete Aggregates 39 4.2.1 Basin-Fill Sources 39 4.2.2 Rock Sources 50 5.1 Road-Base Aggregates 51 5.1.1 Class RBIA Sources 51 5.1.2 Class RBIA Sources 51 5.1.2 Class RBIA Sources 52	1.0	INTR	ODUCTION	1
1.3 Objectives				
1.4 Scope				
2.0 GEOLOGIC SETTING				
2.1 Physiography		1.4	scope	0
2.2 Location and Description of Geologic Units 8	2.0	GEOL	OGIC SETTING	8
2.2 Location and Description of Geologic Units 8		2 1	Dhugiographu	Q
2.2.1 Rock Units				
2.2.2 Basin-Fill Units		2.2		
3.0 ROAD-BASE AGGREGATES EVALUATION				
3.1 Study Approach			2.2.2 Dasin Fill Onics	
3.1.1 Requirements for Road-Base Aggregates	3.0	ROAD-	-BASE AGGREGATES EVALUATION	12
3.1.1 Requirements for Road-Base Aggregates		3.1	Study Approach	12
3.1.2 Data Acquisition and Analysis		•••		
3.1.3 Presentation of Results				
3.1.4 Classification of Road-Base				
3.2 Sources of Road-Base Aggregates				• •
3.2 Sources of Road-Base Aggregates			Aggregates	17
3.2.2 Rock Sources		3.2	Sources of Road-Base Aggregates	19
4.0 CONCRETE AGGREGATES EVALUATION				
4.1 Study Approach			3.2.2 Rock Sources	24
4.1.1 Requirements for Concrete Aggregates 26 4.1.2 Data Acquisition and Analysis 28 4.1.3 Presentation of Results 34 4.1.4 Classification of Concrete Aggregates 36 4.2 Sources of Concrete Aggregates 39 4.2.1 Basin-Fill Sources 39 4.2.2 Rock Sources 48 5.0 CONCLUSIONS 50 5.1 Road-Base Aggregates 51 5.1.1 Class RBIa Sources 51 5.1.2 Class RBIb Sources 52	4.0	CONC	RETE AGGREGATES EVALUATION	26
4.1.1 Requirements for Concrete Aggregates 26 4.1.2 Data Acquisition and Analysis 28 4.1.3 Presentation of Results 34 4.1.4 Classification of Concrete Aggregates 36 4.2 Sources of Concrete Aggregates 39 4.2.1 Basin-Fill Sources 39 4.2.2 Rock Sources 48 5.0 CONCLUSIONS 50 5.1 Road-Base Aggregates 51 5.1.1 Class RBIa Sources 51 5.1.2 Class RBIb Sources 52			Obudu Barranda	26
4.1.2 Data Acquisition and Analysis		4.1		
4.1.3 Presentation of Results				
4.1.4 Classification of Concrete Aggregates				_
4.2 Sources of Concrete Aggregates				
4.2.1 Basin-Fill Sources		A 2		
4.2.2 Rock Sources		7.4		
5.0 <u>CONCLUSIONS</u>				
5.1 Road-Base Aggregates				
5.1.1 Class RBIa Sources	5.0	CONC	<u>LUSIONS</u>	50
5.1.1 Class RBIa Sources		5.1	Road-Base Aggregates	51
5.1.2 Class RBIb Sources 52		<b>-•</b> •		

# TABLE OF CONTENTS (cont'd)

			Page
	5.2	Concrete Aggregates 5.2.1 Class CA1 Sources 5.2.2 Class CB Sources 5.2.3 Class CC1 Sources 5.2.4 Class CC2 Sources	52 52 52 54 54
6.0	RECO	MMENDATIONS FOR FUTURE STUDIES	55
	6.1 6.2	Sources of Road-Base Aggregates	55 55
7.0	BIBL	IOGRAPHY	57
		LIST OF APPENDICES	
Appe	ndix		
A		Summary of Field and Laboratory Test Data, Pahroc Valley, Nevada	A-1
В		Summary of Field Petrographic and Grain-size Analyses Data, Pahroc Valley, Nevada	B-1
С		Trench Logs	C-1
_	-1	Flow Diagram, Road-Base Aggregates Testing	D-1
D-	-2	Flow Diagram, Concrete Trial Mix Design and Testing	D-2
E	-1	Chemical Analyses of Cement, Fly Ash, and Water	
_		used in Concrete Trial Mix Designs	E-1
_	-1	Unified Soil Classification System	F-1
_	-2 -3	Summary of Caliche Development	F-2
G.		Ertec Western Geologic Unit Cross Reference	F-3
G		Cross Reference from Map Number to Verification Activity, Pahroc Valley, Nevada	G-1
		LIST OF FIGURES	
Figur			_
Numbe	<u>er</u>		Page
1		Detailed Aggregate Resources Study	
_		Pahroc Study Area, Nevada	2
2		Utah-Nevada Regional Aggregate Studies	4
3		Valley-Specific Aggregate Resources Study	_
4		Areas, Nevada-Utah	5
**		Aggregates, Class RBIa, Pahroc Study Area,	
		Nevada	21
		***************************************	~ (

# TABLE OF CONTENTS (cont'd)

	LIST OF FIGURES	
Figure Number		Page
5	Grain-Size Distribution Envelopes, Concrete Aggregates, PA-A-(6-10), Pahroc Study Area, Nevada	41
6	Aggregates, Class CB, Pahroc Study Area, Nevada	46
	LIST OF TABLES	
Table Number		
1	Aggregate and Trial Mix Tests, Concrete Aggregates Evaluation, Pahroc Study Area, Nevada	31
2	Concrete Trial Mix Design Criteria, Pahroc Study Area, Nevada	32
3	Concrete Trial Mix Test Results, PA-A-(6-10) Pahroc Study Area, Nevada	43
	LIST OF DRAWINGS	
Drawing Number		
1	Field Station and Selected Existing Data Site Locations, Detailed Aggregate Resources Study, Pahroc Study Area, Nevada	In Pockets
2	Road-Base Aggregate Resources Map, Detailed Aggregate Resources Study, Pahroc Study Area, Nevada	at End of
3	Concrete Aggregate Resources Map, Detailed Aggregate Resources Study, Pahroc Study Area, Nevada	Report

#### EXECUTIVE SUMMARY

This report contains the Detailed Aggregate Resources Study (DARS) evaluation for the Pahroc study area. It is the fourth in a series of reports that contain detailed aggregate information on the location and quality of basin-fill and rock sources of road-base and concrete aggregates. Field reconnaissance, laboratory testing, and existing data from other Ertec Western, Inc. (formerly Fugro National, Inc.) investigations and the Nevada Department of Highways provide the basis for the findings presented in this report.

#### ROAD-BASE AGGREGATES

Potential road-base aggregate sources were classified as follows:

- Class RBIa Basin-fill or rock sources containing materials suitable for use as road-base aggregates; based on acceptable laboratory aggregate test results.
- Class RBIb Basin-fill sources containing materials suitable for use as road-base aggregates; based on correlation with Class RBIa source areas.
- Class RBII Potential basin-fill sources of materials suitable for use as road-base aggregates; based on photogeologic interpretations, field observations, and limited or inconclusive sieve analysis and/or abrasion data.

Assignment of an aggregate source to one of the above three classes was determined from laboratory test results (gradation, abrasion and, to a lesser extent, soundness) and geomorphological and compositional correlations.

V

Results of this evaluation are presented on a 1:62,500 scale aggregate resources map (Drawing 2) and are summarized as follows:

Class RBIa Sources: Four basin-fill sources consisting of goodto high-quality aggregates acceptable for use as road-base construction materials have been located in western Pahroc and northern Pahranagat valleys. All are alluvial fan deposits (Aaf).

> One crushed-rock source which yielded goodto high-quality aggregates acceptable for use as road-base construction materials has been delineated within the study area. This source is a fairly limited outcrop of calcareous sandstone classified as dolomite rock (Do).

Class RBIb Sources: Four basin-fill sources within the study area are defined as potential sources of good- to high-quality road-base aggregates. Geomorphological and compositional similarities were used to correlate these units to tested RBIa deposits. Deposits are all alluvial fans and are confined to western Pahroc and northern Pahranagat valleys.

Class RBII Sources:

Several potential basin-fill aggregate sources are located throughout the study All of these sources are alluvial fans that have been classified on the basis of limited field and laboratory data.

#### CONCRETE AGGREGATES

A classification system consisting of five classes was developed for the concrete aggregates evaluation to present potential basin-fill and crushed-rock sources. Although most rock sources will supply coarse concrete aggregates, their delineation was not an objective of this study. Assignment of an aggregate source to one of the five classes was determined from laboratory test results (trial concrete mixes and gradation, abrasion, and soundness of aggregates) and geomorphological and compositional correlations. The emphasis of this study was the evaluation of the concrete-making properties (especially 28-day compressive strengths) of potential aggregates when used in trial concrete mixes.

- Class CA1 Basin-fill or rock sources containing aggregates that produced trial mix concrete with 28-day compressive strengths equal to or greater than 6500 psi.
- Class CA2 Basin-fill or rock sources containing aggregates that produced trial mix concrete with 28-day compressive strengths less than 6500 psi.
- Class CB Basin-fill or rock sources containing aggregates potentially suitable for use in concrete; based on acceptable laboratory aggregate test results.
- Class CC1 Basin-fill or rock sources containing aggregates potentially suitable for use in concrete; based on correlation with Class CA1 and CA2 source areas.
- Class CC2 Basin-fill sources containing aggregates potentially suitable for use in concrete; based on correlation with Class CB source areas.

The following three trial mixes were used to obtain a range of compressive strength values; however, only Mix 3 results were used to classify sources. In all three trial mixes, fly ash, as a pozzolan, replaced 20 percent of the cement by weight.

- o Mix 1 7.5 sacks of cement per cubic yard of concrete and 1.5-inches maximum aggregate size;
- o Mix 2 8.5 sacks of cement per cubic yard of concrete and 1.5-inches maximum aggregate size; and
- o Mix 3 ~ 8.5 sacks of cement per cubic yard of concrete, 0.75-inch maximum aggregate size, and a superplasticizer.

Results of this evaluation are presented on a 1:62,500 scale aggregate resources map (Drawing 3) and summarized as follows:

#### Class CA1

One basin-fill source in the area contained aggregates that, when used in Mix 3, produced 28-day compressive strengths greater than 6500 psi. This source is an alluvial fan (Aaf) located in northern Pahranagat Valley.

High-quality, fine aggregate sources are lacking or of limited extent within the study area.

#### Class CB Sources:

Three basin-fill sources consisting of goodto high-quality aggregates, potentially acceptable for use as concrete construction materials, were delineated in western Pahroc and northern Pahranagat valleys. All are alluvial fan deposits.

The quality of fine aggregates tested within this class ranges from poor to satisfactory.

Class CC1 Sources: One alluvial fan in the study area is classified as a potential source of concrete It is correlated to the Class aggregates. CA1 source based on geomorphological and compositional similarities.

#### Class CC2 Sources:

Four alluvial units located along the western side of Pahroc Valley are potential sources of aggregates suitable for use in concrete. They are correlated to Class CB units on the basis of geomorphological and compositional similarities.

#### CONCLUSIONS

Sufficient quantities of coarse and fine aggregates suitable for use as road-base and/or concrete construction material are available in the Pahroc study area. Laboratory test results indicate that the quality of the coarse aggregates ranges from good to excellent, and the quality of the fine aggregates ranges from poor to satisfactory. Most of the aggregate sources are confined to the west side of Pahroc Valley and the northern end of Pahranagat Valley.

# RECOMMENDATIONS

Additional aggregate field investigations and laboratory testing will be required to further refine the physical and chemical characteristics of road-base and concrete aggregate sources as borrow areas prior to the initiation of construction.

#### 1.0 INTRODUCTION

# 1.1 STUDY AREA

This report presents the results of the Detailed Aggregate Resources Study (DARS) for the Pahroc study area (Figure 1). Pahroc study area is located in south-central Lincoln County, Nevada, and includes Pahroc Valley and the extreme northern part of Pahranagat Valley. Pahroc Valley is bounded on the east by the North and South Pahroc ranges and on the west by the Hiko Range. Northern Pahranagat Valley is bounded on the east by the Hiko Range and on the west by the North Pahranagat and Seaman ranges. U.S. Highway 93 passes east-west through the study area, and State Highway 38 passes north-south through Pahranagat Valley. A network of graded roads and four-wheel-drive trails provide additional access to most of the study area. Pahroc and Pahranagat valleys are mainly undeveloped desert rangeland administered by the Bureau of Land Management (BLM). Valley contains some private land along its central axis. nearest support community is Ash Springs, located approximately 5 miles (8 km) south of the intersection of U.S. Highway 93 and State Highway 38.

#### 1.2 BACKGROUND

Aggregate resources studies for the MX program were introduced in 1977 with the investigation of Department of Defense (DoD) and BLM lands in California, Nevada, Arizona, New Mexico, and Texas (FN-TR-20D). Refinement of the MX siting area added portions of Utah and Nevada that were not evaluated in this


**E**ttec

initial Aggregate Resources Evaluation Investigation (AREI). This additional area, defined as the Utah-Nevada aggregate resources study area, was examined in the fall of 1979, and a second regional aggregate resources report was submitted on 3 March 1980 (Figure 2).

Both regional aggregate investigations consisted of the compilation and evaluation of existing data with limited field reconnaissance, sample collection, and laboratory aggregate testing. Only general information on the location, quality, and quantity of aggregates was provided.

Subsequent to the regional studies, Valley-Specific Aggregate Resources Studies (VSARS) were started in FY 79. The primary objective of these continuing studies is to provide additional information on potential aggregate sources in specified valleys and in the areas immediately surrounding them. Existing exposures of potential basin-fill and rock aggregate sources are sampled and subjected to a suite of laboratory tests. Results of these tests are used to classify coarse and fine basin-fill and crushed-rock aggregates for suitability as concrete and road-base construction materials.

The aggregate sources presented in the VSARS are to be used as a guide for preliminary construction planning and the selection of areas for more detailed-aggregate evaluations. To date, field investigations have been completed for 16 valley areas with final reports submitted for 11 valley areas (Figure 3).



Field investigations for remaining valleys in the designated deployment area are planned in FY 81 and FY 82.

The DARS were initiated in FY 81 to further analyze and refine potential sources of coarse and fine basin-fill and crushed-rock aggregates identified during the VSARS. These studies consist of both road-base (Section 3.0) and concrete (Section 4.0) aggregate evaluations. The major consideration was to further evaluate basin-fill deposits as potential sources of road-base and concrete aggregates. Limited new data were developed on crushed-rock sources.

#### 1.3 OBJECTIVES

The objectives of the Detailed Aggregate Resources Study are as follows:

#### Road-Base Aggregates Evaluation

- o Refine potential basin-fill and rock sources (initially identified in VSARS) for road-base aggregates; and
- o Provide additional laboratory test data on the general quality of basin-fill aggregates for use as road-base material.

#### Concrete Aggregates Evaluation

- o Refine the areal extent of the most acceptable VSARS basin-fill and rock concrete aggregate sources; and
- o Provide additional laboratory testing information on the quality and the concrete-making properties of potential coarse and fine basin-fill and crushed-rock aggregates.

#### 1.4 SCOPE

The scope of the two evaluations required office and field studies and included the following:

a. Compilation and analysis of appropriate existing data on the quality and quantity of potential road-base and concrete

aggregates. Major sources of data were other Ertec investigations for the siting of the MX system and the Nevada Department of Highways.

- b. Initial and final basin-fill deposit differentiation based on geomorphology, grain size, lithology, and aerial photography and topographic map interpretation. Initial and final rock unit divisions based on evaluations of aerial photography and published geologic maps.
- c. Staking and permitting on selected BLM lands. Appropriate basin-fill trench locations for samples of road-base and concrete aggregates were determined from items a and b and a brief field reconnaissance.
- d. Backhoe excavation of staked and permitted basin-fill locations, sampling when gravel percentage exceeded 30 percent, or when suitable fine aggregates for concrete mixes were present. Selection and sampling of acceptable crushed-rock sources of coarse aggregates for concrete mixes.
- e. Valley-wide field reconnaissance utilizing aerial photography and petrographic and grain-size analyses to determine lateral extent and acceptability of basin-fill deposits.
- f. Laboratory tests to supplement available existing data for the determination of the suitability of specific basin-fill and rock units as sources of road-base or concrete aggregates. Trial (check) concrete mixes were made to evaluate the basic concrete-making properties of selected concrete aggregate sources as well as engineering properties of hardened concrete.
- g. Development and application of road-base and concrete materials classification systems that textually and graphically depict the locations of the most suitable aggregate sources in the study area. The depiction and discussion of areas that are unsuitable or have a low probability for use were not done.

#### 2.0 GEOLOGIC SETTING

#### 2.1 PHYSIOGRAPHY

The Pahroc study area lies within the Basin and Range Physiographic Province. The primary physiographic features of the area are the uplifted mountain ranges and the down-dropped, alluvium-filled basins. These north to north-northeast trending features are controlled by block-faulting are typical of the Basin and Range province. Elevations in the valley floor in Pahroc Valley range from approximately \$100 to 5000 feet (1250 to 1524 m) and in Pahranagat Valley from 3900 to 4400 feet (1189 to 1341 m).

Mountain ranges flanking Pahroc Valley include the North and South Pahroc ranges and the Hiko Range and in Pahranagat Valley, the Hiko, North Pahrangat, and Seaman ranges. The Pahroc study area adjoins Delamar and Dry Lake valleys to the east. Topographic relief between mountain crests and basin floors varies from 3550 feet (1882 m) in Pahroc Valley to 2300 feet (701 m) in Pahrangat Valley. Both valleys within the study area have open drainage systems.

#### 2.2 LOCATION AND DESCRIPTION OF GEOLOGIC UNITS

Paleozoic and Cenozoic rocks are found predominantly in the mountains within the study area and only infrequently as outliers within the valley fill. The Paleozoic rocks consist of limestone, dolomite, and quartzite with interbedded sandstone and shale. These units are generally exposed along the northern margins of and between the study area valleys; where they are

not exposed, they underlie younger geologic units. Cenozoic rocks unconformably overlie Paleozoic rocks and generally consist of undifferentiated volcanic and intravolcanic sedimentary deposits. Unconsolidated Cenozoic deposits lie unconformably above all older units and consist primarily of alluvial, lacustrine, and stream-channel and terrace deposits.

Specific Paleozoic and Cenozoic geologic units have been grouped into two rock and one basin-fill categories for use in discussing potential sources of aggregates. The grouping of the units was based on similarities in physical and chemical characteristics and map-scale limitations. The resulting categories simplify discussion and presentation without altering the conclusions of the study.

#### 2.2.1 Rock Units

Dolomite rocks (Do) and carbonate rocks undifferentiated (Cau) are the primary potential sources of crushed-rock aggregates in the study area valleys. While all other rock units may locally supply aggregates, insufficient test data prohibit their consideration as major aggregate sources, and they will not be discussed in this report.

Materials classified as dolomite (Do) include the limited occurrence of an intraformational calcareous sandstone at the top of the Middle Devonian Simonson Dolomite. It crops out in Pahroc Valley on the east side of the Hiko Range. This rock is typically hard, medium-grained, and slightly weathered with well-developed jointing.

Materials classified as undifferentiated carbonate rocks (Cau) include thick, complex sequences of limestone and dolomite with occasional interbeds of sandstone or quartzite and intraformational conglomerate. The formation in this unit is the Upper Devonian Guilmette Formation. It crops out in the North Pahranagat Range and to a limited extent in the Hiko Range. These rocks are typically light- to dark-grey in color, thin- to very thick-bedded, durable, locally sandy or conglomeratic, fossiliferous, and resistant cliff-formers.

#### 2.2.2 Basin-fill Units

The basin-fill geologic units within the study area that are potential sources of coarse and fine aggregates are alluvial fans deposits (Aaf). All other basin-fill units may locally supply aggregates but are not considered major sources and will not be discussed in this report.

Alluvial fans are the most extensive potential sources of basin-fill aggregates within the study area. They occur on the east flanks of the Hiko Range north of U.S. Highway 93, west of the North Pahroc Range, and east of the North Pahranagat Range. Alluvial fan deposits are typically heterogeneous to poorly stratified mixtures of boulders, cobbles, gravel, sand, silt, and clay. The units are predominantly sandy gravel.

Most alluvial fan deposits have developed soil horizons consisting of silty, clayey sand, 1 to 2 feet (0.3 to 0.6 m) in thickness, overlying a zone of carbonate accumulation (caliche). The

caliche horizon generally ranges in thickness from 1 to 1.5 feet (0.3 to 0.5 m) and exhibits Stage I to III development with Stage II being most common (Appendix F).

#### 3.0 ROAD-BASE AGGREGATES EVALUATION

#### 3.1 STUDY APPROACH

The primary objective of the road-base aggregate study was to evaluate the suitability of basin-fill and rock aggregates for use as road base. Two important considerations were applied to basin-fill aggregate sources identified as potentially suitable in VSARS, refinement of source boundaries, and additional laboratory tests to further evaluate physical and chemical characteristics. Sources of crushed-rock aggregates were refined using only existing data, published geologic maps, and limited photogeologic interpretations. Information on potential rock sources for use as road-base aggregates was not specifically collected for this evaluation. Only existing VSARS data and data developed from the concrete aggregates evaluation (Section 4.0) were assessed.

The study approach for the road-base aggregates evaluation required a review of an in-progress Ertec Verification (E-TR-27-PA-I and II) report for Pahroc Valley and previous aggregate reports (FN-TR-20D and FN-TR-37-a) for Pahroc and Pahranagat valleys. This data base helped define the scope of the road-base materials investigation which included office and field photogeologic and topographic interpretations, field reconnaissance, and collection and laboratory testing of basin-fill samples.

# 3.1.1 Requirements for Road-Base Aggregates

For the purpose of this report, road-base aggregates are defined using the Nevada Department of Highways (1976) classification of

Type I Class A aggregate base. The requirements for aggregates suitable for such a base are as follows:

#### Gradation:

	Percent Passing
Sieve Size	by Weight
1.5 inches	100
1.0 inch	80~100
No. 4	30~ 65
No. 16	15~ 40
No. 200	2- 12
Fractured Faces	35 percent, minimum
Plasticity Index	
Liquid Limit	35 maximum

Resistance (R value) ...... 70 minimum Percent Wear (500 Rev.) ..... 45 percent, maximum

During the road-base aggregate studies, gradation and percent wear were the two primary criteria used to evaluate potential source areas. Magnesium sulfate (MgSO<sub>4</sub>) soundness tests were performed on selected coarse aggregate samples to gain additional information related to the effects of weathering on aggregates. Soundness losses exceeding 18 percent were considered potentially unacceptable (American Society of Testing and Materials, 1978). The remaining requirements were not evaluated during this study.

#### 3.1.2 Data Acquisition and Analysis .

Office studies for the road-base aggregates evaluation required preliminary basin-fill and rock unit differentiation based on photogeologic interpretations and published topographic and geologic maps. All available data on basin-fill, grain-size gradations were compiled to estimate gravel content for the defined basin-fill units.

The field program involved backhoe excavation of 10 trenches selected during office studies and initial field reconnaissance. Trenches were excavated and sampled in groups of two or three, 0.1 to 0.2 mile (0.2 to 0.3 km) apart, to characterize individual basin-fill units. Completion depths ranged from 12 to 15 feet (3.7 to 4.6 m) and, where collected, representative samples averaged 100 pounds (45 kg) per trench.

Due to gradation variability in basin-fill deposits, field limits of 30 percent or more gravel and 20 percent or less silt and clay were established as basic aggregate grain-size distribution requirements. Gravel is defined as coarse aggregates which pass the 3.0-inch (75-mm) sieve and are predominantly retained on a No. 4 (4.75-mm) sieve. Aggregates larger than 3.0 inches (cobbles and boulders) were generally present in the materials investigated but were not included in the laboratory samples because of sample-size limitations. Silt and clay particles are defined as material passing through a No. 200 sieve (0.0029-inch [0.075-mm]).

Field studies also included six petrographic and grain-size data field stops and valley-wide photogeologic field reconnaissance. These analyses were performed to supplement and confirm office studies and to provide a data base for lithologic and gradation correlations of basin-fill units.

Laboratory testing that included three sieve analyses, one abrasion test, and one MgSO<sub>4</sub> soundness test was performed to

broaden the existing data base during the road-base aggregates evaluation. Confirmation test data (gradation, abrasion, and soundness tests) from the concrete aggregates evaluation (Section 4.0) were also used to supplement test data for the road-base aggregates evaluation.

The scope of the study did not allow sample collection and laboratory testing of all potential road-base aggregate sources. Existing data and field petrographic and grain-size analyses were used to correlate lithologic and gradation properties to basin-fill units which were not sampled. An important element of this correlation procedure was the use of aerial photography to help delineate the lateral extent of basin-fill deposits. Photogeologic and field observations ascertained geomorphological and topographical relationships of basin-fill units and the source rock lithology and distribution of predominantly gravelly materials.

#### 3.1.3 Presentation of Results

Results of the road-base aggregates evaluation are presented in the form of text, figures, 1:62,500 scale drawings, and appendices. Drawing 1 shows the locations of all the data points used in the Detailed Aggregate Resources Study. The data points are grouped by study type and assigned categorized map numbers. VSARS data points are designated by map numbers 1 to 199 and correspond to map numbers in the appendix table of the Pahroc area VSARS report (FN-TR-37-a). DARS data points are assigned map number groups 200 to 299 for trench locations and 300 to 399

for petrographic and grain-size data stop locations. Verification data points are assigned the map number group 400 to 599. Appendix Table G-1 converts map number to Pahroc Verification Report (E-TR-27-PA-I and II) activity type and number for direct reference.

Drawing 2 presents the locations of all potential road-base aggregate sources, DARS trenches, select VSARS data stops, and field petrographic and grain-size data stops in the study area. Geologic unit symbols used in Drawing 2 relate to standard geologic nomenclature whenever possible. A conversion table relating these symbols to the geologic unit nomenclature used in other Ertec reports is contained in Appendix Table F-3.

A solid contact line separates basin-fill and rock units in Drawing 2 to differentiate these two basic material types. All rock contacts are from published data or limited air-photo interpretation and are dashed. Basin-fill contacts are derived from photogeological mapping with limited field reconnaissance and are also dashed.

Classifications of potential sources of basin-fill and crushed-rock road-base aggregates are distinguished by different patterns. Patterns for basin-fill and rock sources of the same classification are similar, with the basin-fill pattern emphasized by a dark background tone.

The appendices contain tables that summarize the basic field data collected during the course of the study and the subsequent

laboratory test procedures and results. Appendices A and B include DARS trench data and petrographic and grain-size analysis data, respectively. Appendix C contains representative trench logs. Appendix Table D-1 presents a laboratory testing flow diagram for the road-base aggregates evaluation. Appendix F includes three tables describing soil classification, caliche development, and geologic unit cross reference.

# 3.1.4 Classification of Road-Base Aggregates

A classification system was designed to present the most likely locations of potential sources of basin-fill and crushed-rock road-base aggregates. It was developed from an evaluation as well as from an extrapolation of all available data.

This classification system is primarily based on laboratory test results (gradation and abrasion and, to a lesser extent, soundness) and geomorphological and compositional correlations. The classification is presented in hierarchy form; classification of the highest potential source areas is described first and classification of the lowest potential source areas is described last.

Class

Explanation

**RBIa** 

Basin-fill or rock sources containing materials suitable for use as road-base aggregates; based on acceptable laboratory aggregate test results.

Class RBIa includes those source areas where the potential for suitable road-base aggregates is the highest. Each delineated

area has been sampled and tested. In order to assign Class RBIa to a basin-fill deposit, the source must satisfy the overall requirements outlined in Section 3.1.1.

Class

#### Explanation

RBIb

Basin-fill sources containing materials suitable for use as road-base aggregates; based on correlation with Class RBIa source areas.

Class RBIb basin-fill deposits are correlated to tested RBIa deposits on the basis of limited laboratory sieve analysis data and field observations. Field observations included petrographic and grain-size analyses which provided data on lithology of adjacent source rock and general amounts and lithologies of gravel present in the basin-fill units. Photogeologic interpretations were also used to correlate Class RBIb deposits to RBIa deposits. Specific geomorphological parameters included surface texture, drainage patterns, relative relief, and topographic profiles.

Class

#### Explanation

RBII

Potential basin-fill sources of materials suitable for use as road-base aggregates; based on photogeologic interpretations, field observations, and limited or inconclusive sieve analysis and/or abrasion data.

Class RBII includes poorly defined, basin-fill aggregate sources. Field observations and inconclusive field and laboratory data indicate these deposits may be potentially acceptable for use as road-base aggregate sources.

**Ertec** 

All classifications are based on limited data. Additional field reconnaissance, testing, and case history studies are needed to confirm adequacy, delimit exact areal boundaries, and refine chemical and physical characteristics.

## 3.2 SOURCES OF ROAD-BASE AGGREGATES

The potential basin-fill and rock units defined for use as road-base aggregates in the Pahroc study area include alluvial fan deposits (Aaf) and a dolomite rock unit (Do).

#### 3.2.1 Basin-Fill Sources

All three classes of road-base aggregates, RBIa, RBIb, and RBII, are present in the basin-fill units of Pahroc or northern Pahranagat Valley (Drawing 2).

#### 3.2.1.1 Class RBIa


Class RBIa sources within the study area are located along the east side of the Hiko Range in Pahroc Valley and on the east side of the North Pahranagat Range in northern Pahranagat Valley. There are four Class RBIa basin-fill deposits composed of alluvial fan units (Aaf) within the study area.

In Pahroc Valley, the Class RBIa deposit consists of well-graded, subangular to subrounded sandy gravel. The gravel content of the deposit ranges from 43 to 56 percent. The sand content is about 45 percent. The silt and clay content of the deposit (below the overburden layer) is one percent or less. These deposits commonly consist of 72 to 78 percent carbonate clasts, seven to 22 percent quartzite clasts, and two percent or less volcanic clasts.

In northern Pahranagat Valley, three Class RBIa deposits consist of poorly to well-graded, subangular to subrounded sandy gravel and gravelly sand. The gravel content of the deposits range from a low of 40 percent to a high of 75 percent. Sand content ranges from 20 to 40 percent. The silt and clay content of the deposits (below the overburden layer) ranges from four to 11 percent. These deposits commonly consist of 72 to 90 percent carbonate clasts, generally less than 22 percent quartzite clasts, and less than three percent volcanic clasts. The northernmost Class RBIa deposit in Pahranagat Valley differs from the other Class RBIa deposits in that it contains a higher percentage of volcanic clasts.

The gradation of Class RBIa deposits approximates the grain-size distribution requirements stated in Section 3.1.1 (Figure 4). There is generally a deficiency of coarse and fine gravel passing the 1.5-inch to No. 4 sieves and a slight excess of fine sand passing the No. 50 to No. 200 sieves. Sufficient oversize material is available for crushing to provide additional aggregates of all sizes. Processing of most RBIa deposits will be necessary to conform to the design gradation requirements.

It has been observed that variations in grain-size gradations occur within a deposit depending on sample location. In general, gradations within a deposit are finer near the valley axis and coarser near mountain fronts. Due to access restrictions, samples were generally collected at distal and medial locations within each deposit.



<del>---</del>

REQUIRED GRAIN-SIZE DISTRIBUTION ENVELOPE FOR TYPE I CLASS A, ROAD-BASE AGGREGATES (NEVADA STATE DEPARTMENT OF HIGHWAYS, 1976).



GRAIN-SIZE DISTRIBUTION ENVELOPE OF BASIN-FILL AGGREGATES POTENTIALLY SUITABLE FOR ROAD BASE.



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/APRCE-MX

GRAIN-SIZE DISTRIBUTION ENVELOPES
ROAD-BASE AGGREGATES, CLASS REA
PAHROC STUDY AREA, NEVADA

6 JUN 81

FIGURE 4

Laboratory abrasion tests performed on samples from all Class RBIa deposits show a fairly narrow range from 24 to 35.5 percent wear. Laboratory MgSO<sub>4</sub> soundness test results on coarse aggregates from Pahranagat Valley range from 4.1 to 18.2 percent loss. One MgSO<sub>4</sub> soundness test result on coarse aggregates from Pahroc Valley yielded a 13 percent loss. MgSO<sub>4</sub> soundness test results on fine aggregates from both valleys ranged from 17.4 to 35.3 percent loss. A NaSO<sub>4</sub> soundness test performed on a fine aggregates sample from Pahranagat Valley yielded a loss of 2.8 percent. Abrasion test results are within acceptable values. Coarse aggregates generally have acceptable MgSO<sub>4</sub> soundness test results, but fine aggregates do not.

Class RBIa deposits have areal extents ranging from approximately 0.25 to 3.1 mi $^2$  (0.65 to 8.0 km $^2$ ). The thickness of these deposits is estimated to be at least 25 feet (7.6 m). Generally, 70 to 85 percent of the material in these deposits will be suitable for use as road-base aggregates.

## 3.2.1.2 Class RBIb

Class RBIb basin-fill sources consist of alluvial deposits that have been correlated to Class RBIa units and, therefore, are considered to contain material acceptable for use as road-base aggregates. Class RBIb basin-fill sources are located on the east side of the Hiko Range in Pahroc Valley and on the east side of the North Pahranagat Range in northern Pahranagat Valley. There are four Class RBIb basin-fill deposits composed of alluvial fan units (Aaf) within the study area.

Since Class RBIb basin-fill deposits are correlated to Class RBIa deposits, they possess the same general characteristics as the RBIa deposits, well-graded, subangular to subrounded sandy gravel and gravelly sand composed of predominantly carbonate clasts with secondary quartzite and volcanic clasts.

Although variations in grain-size gradations will occur, depending on sample location within the deposit and the proximity of the deposit to its source area, Class RBIb deposits are interpreted to have gradation distributions similar to RBIa deposits.

The Class RBIb deposits range in surface area from approximately 0.1 to  $3.4 \text{ mi}^2$  (0.3 to  $8.8 \text{ km}^2$ ). The thickness of these deposits is estimated to be at least 25 feet (7.6 m). Generally, from 70 to 85 percent of the material in these deposits will be suitable for use as road-base aggregates.

### 3.2.1.3 Class RBII

Sources of Class RBII basin-fill aggregates are alluvial fan deposits (Aaf) that are potentially acceptable for use as road base. These deposits have been classified on the basis of limited field and laboratory data collected during this and other Ertec studies.

Class RBII deposits are located in Pahroc Valley east of the Hiko Range and west of the North Pahroc Range. All of the Class RBII deposits are alluvial fan units (Aaf).

Limited laboratory and field data used to define the Class RBII deposits on the east side of the Hiko Range (west side of Pahroc

Valley) indicate that they are compositionally similar to RBIa and RBIb deposits, consisting of sandy gravel and gravelly sand composed predominantly of carbonate clasts. Class RBII deposits west of the North Pahroc Range (east side of Pahroc Valley) consist of gravelly sand composed predominantly of carbonate clasts. Gravel content varies from 10 to 50 percent. There may be considerable variations from this general description within individual deposits. Although no DARS gradation data exist for Class RBII deposits in the study area, it is assumed that variations in gradation are generally similar to those of Class RBIA deposits. The areal extent of all Class RBII deposits ranges from approximately 0.3 to 7.0 mi<sup>2</sup> (0.8 to 20.5 km<sup>2</sup>).

# 3.2.2 Rock Sources

The study approach used to evaluate road-base aggregates emphasized the analysis of basin-fill deposits and dictated that only previously tested, crushed-rock sources be discussed and classified. As a consequence, other rock units potentially suitable as sources of crushed-rock road-base aggregates are not included or described in this study.

The source of crushed rock for use as road-base aggregates is an intraformational calcareous sandstone assigned to the dolomite rocks (Do) geologic unit. This Class RBIa source is located on the west side of Pahroc Valley, east of the Hiko Range.

Laboratory abrasion and MgSO4 soundness test results are 35.5 percent wear and 3.6 percent loss, respectively. These test

results are well within acceptable ranges for road-base aggregates.

### 4.0 CONCRETE AGGREGATES EVALUATION

## 4.1 STUDY APPROACH

The purpose of the concrete aggregates evaluation is to determine the suitability of aggregates within the Pahroc study area for use in concrete. To accomplish this, two objectives have been established:

- o Evaluate the basic physical and chemical characteristics of the aggregates; and
- o Determine the concrete-making properties of the aggregates.

The study approach required to achieve these objectives included a review of in-progress Ertec Verification (E-TR-27-PA-I and II) and previous Ertec aggregate reports (FN-TR-20D and FN-TR-37-a). This data base helped define the scope of the concrete aggregates investigation and included office and field photogeologic and topographic interpretations, field reconnaissance, and collection and laboratory testing of basin-fill and rock samples.

# 4.1.1 Requirements for Concrete Aggregates

The following requirements for aggregates and concrete (made using these aggregates) were established using criteria from the American Society of Testing and Materials (1979), the "Concrete Manual" prepared by the United States Department of the Interior (1975), and from Milos Polivka (1981, personal communication).

### 1. Aggregates

o Gradation - The aggregate gradation specifications used by the American Society of Testing and Materials (1979, C 33) were selected to evaluate the samples tested. These grading specifications follow.

### Coarse Aggregates

Sieve Size	Percent Passing by Weight	Sieve Size	Percent Passing by Weight
2 inches	100	1 inch	100
1.5 inches	95-100	0.75 inch	90-100
1 inch		0.5 inch	
0.75 inch	35-70	0.375 inch	20~55
0.50 inch		No.4	0-10
0.375 inch No.4	10-30 0-5	No.8	0-5

### Fine Aggregates

Sieve Size	Percent Passing by Weight
0.375 inch	100
No.4	95~100
No.8	80~100
No.16	50~85
No.30	25~60
No.50	10-30
No.100	2-10
No. 200	

- o Abrasion Los Angeles Machine abrasion losses for coarse aggregates are not to exceed 50 percent.
- o Soundness Five-cycle magnesium sulfate (MgSO<sub>4</sub>) soundness losses are not to exceed 18 percent and 15 percent for coarse and fine aggregates, respectively. Although not a requirement for the evaluation, five-cycle sodium sulfate (NaSO<sub>4</sub>) soundness tests are performed on samples that failed MgSO<sub>4</sub> testing. Resultant losses are not to exceed 12 percent and 10 percent for coarse and fine aggregates, respectively.
- o Reactivity Aggregates are to be nonreactive to alkalisilica and alkali-carbona'e rock tests. Results are incomplete and will be submitted as an addendum to this report.

### 2. Concrete

o Compressive Strength - The primary concrete requirement is a 28-day compressive strength equal to or greater than 6500 psi.

- o Static Modulus of Elasticity Values of 3 to 6 million psi at 28 days required.
- o Splitting Tensile Strength Ten percent or less of the compressive strength value at 28 days required.
- o Ultimate Drying Shrinkage Values of 0.03 to 0.10 percent (300 to 1000 millionths) required.

### 4.1.2 Data Acquisition and Analysis

# 4.1.2.1 Office Studies

Office studies for the concrete aggregates evaluation required preliminary basin-fill and rock-unit differentation based upon photogeologic interpretations and published topographic and geologic maps. All available data on basin-fill, grain-size gradations were compiled to estimate gravel content for the defined basin-fill units. All available test data on the aggregate properties of basin-fill and rock units were compiled to select sample locations in units previously tested and found preliminarily acceptable for use as sources of concrete aggregates.

### 4.1.2.2 Field Studies

The field program involved backhoe excavation of five trenches selected during office studies and initial field reconnaissance. The trenches were excavated to obtain samples of coarse and fine aggregates (gravel and sand).

Due to gradation variability in basin-fill deposits, field limits of 30 percent or more gravel and 15 percent or less silt and clay were established as basic aggregate grain-size distribution requirements. Gravel is defined as coarse aggregates which pass

the 3.0-inch (75-mm) sieve and are predominantly retained on a No. 4 (4.75-mm) sieve. Silt and clay particles are defined as material passing through a No. 200 sieve (0.0029-inch [0.075-mm]).

The five trenches excavated to collect basin-fill samples for concrete aggregates evaluation were each located 150 feet apart (46 m) to characterize an individual basin-fill unit. Trenches were excavated to depths ranging from 12 to 15 feet (3.7 to 4.6 m). Bulk representative samples averaged 400 pounds (182 kg) per trench.

Field studies also included six petrographic and grain-size data field stops and valley-wide photogeologic field reconnaissance. These analyses were performed to supplement and confirm the office studies and to provide a broader data base for lithologic and gradation correlations of basin-fill units.

## 4.1.2.3 Laboratory Testing

The laboratory aggregate testing program was performed in two phases. The first phase consisted of standard tests for determining the basic properties of the aggregates and included the following:

- o Unit Weights and Voids in Aggregates;
- Standard Specifications for Concrete Aggregates;
- Soundness of Aggregates, Magnesium Sulfate (MgSO<sub>4</sub>) and Sodium Sulfate (NaSO<sub>4</sub>);
- o Sieve Analysis by Washing, less than No. 200 fraction;
- o Fineness Modulus;
- Specific Gravity and Absorption, Coarse and Fine Aggregates;

- o Resistance to Abrasion, Los Angeles Machine;
- o Sieve Analysis, Coarse and Fine Aggregates; and
- o Petrographic Examination of Aggregates for Concrete.

Generally, these tests were performed on aggregates from a location adjacent to a source previously tested and identified as the most promising in the VSARS program. This repetitive testing was done to confirm the suitability of aggregates for concrete (see Section 4.1.1, Requirements for Concrete Aggregates). Table 1 lists the number of tests completed in the Pahroc study area.

The second phase of the testing consisted of an evaluation of the concrete-making properties of the aggregates when used in the following three trial (check) concrete mixes.

- Mix 1 7.5 sacks (94 pounds per sack) of cement per cubic yard of concrete with 1.5-inches maximum aggregate size.
- Mix 2 8.5 sacks (94 pounds per sack) of cement per cubic yard of concrete with 1.5-inches maximum aggregate size.
- Mix 3 8.5 sacks (94 pounds per sack) of cement per cubic yard of concrete with 0.75-inch maximum aggregate size and a superplasticizer.

In the trial mix, fly ash, as a pozzolan, replaced 20 percent of the cement by weight. All concrete trial mix design criteria are presented in Table 2. Samples were collected for one basinfill (coarse and fine aggregates) trial mix. Material greater than 1.5 inches was crushed to conform to gradation requirements. If necessary, coarse and fine aggregates were processed to conform to gradation requirements.

	5		TOTAL NUMBER OF TESTS*				
	ASTM STANDARD TEST	AGGREGATE AND CONCRETE  TEST DESCRIPTIONS 1	BASIN-FILL		ROCK		
	STA	rest beschir flores	CA FA		ROCK FA		
	C29	UNIT WEIGHT AND VOIDS IN AGGREGATE		1	-		
	C33	STANDARD SPECIFICATIONS FOR CONCRETE AGGREGATE		1	-	-	
	C88	SOUNDNESS OF AGGREGATE; Mg SO4/NaSO4	1/-	1/1	-	-	
ES	C117	SIEVE ANALYSIS BY WASHING, < # 200 FRACTION		~	-		
GAT	C125	FINENESS MODULUS	-	1	-	-	
AGGREGATES	C127	SPECIFIC GRAVITY/ABSORPTION, COARSE AGGREGATE	6/2	-/-	-	-	
¥	C128	SPECIFIC GRAVITY/ABSORPTION, FINE AGGREGATE	-/-	3/1	_	-	
	C131	RESISTANCE TO ABRASION, LOS ANGELES MACHINE	1		-	-	
	C136	SIEVE ANALYSIS, COARSE AND FINE AGGREGATE	7	6	_	_	
	C296	PETROGRAPHIC EXAM, OF AGGREGATES FOR CONCRETE	1	1	-	-	
	C39	COMPRESSIVE STRENGTH OF CYLINDRICAL CONCRETE SPECIMENS	2	4	_		
	C138	UNIT WEIGHT, YIELD, AIR CONTENT OF CONCRETE	3 4 30		-	-	
	C143	SLUMP OF PORTLAND CEMENT CONCRETE			-	-	
	C157	LENGTH CHANGE OF HARDENED CEMENT MORTAR AND CONCRETE			_		
	C173	AIR CONTENT OF CONCRETE, VOLUMETRIC METHOD		3		-	
3	C192	MAKING AND CURING CONCRETE SPECIMENS		3			
CONCRETE	C227	POTENTIAL ALKALI-SILICA REACTIVITY, MORTAR-BAR METHOD	-	-	-	-	
8	C466	STATIC MODULUS OF ELASTICITY, POISSONS RATIO OF CONCRETE IN COMPRESSION	2	M	-	-	
	C496	SPLITTING TENSILE STRENGTH OF CYLINDRICAL CONCRETE SPECIMENS	6		-	-	
	C684	MAKING AND TESTING ACCELERATED CURE CONCRETE COMPRESSION THE SPECIMENS	6 -			-	
	222-1-77	SELECTING PROPORTIONS FOR NORMAL AND HEAVY WEIGHT CONCRETE	3 -			-	
	PROP. 3	POTENTIAL ALKALI-CARBONATE ROCK REACTIVITY, LENGTH CHANGE METHOD					
	C39-55 <sup>4</sup>	COEFFICIENT OF LINEAR THERMAL EXPANSION OF CONCRETE	6 (IP) -				

- 1. AMERICAN SOCIETY FOR TESTING AND MATERIALS (1978)
- 2. AMERICAN CONCRETE INSTITUTE (1977)
- 3. MIELENZ (1980) PROPOSED ASTM STANDARD TEST
- 4. UNITED STATES ARMY CORPS OF ENGINEERS (1977)

#### (IP) - TEST IN PROGRESS

 BASIN-FILL SOURCES SUPPLIED SOTH COARSE AND FINE AGGREGATES FOR CONCRETE MIX. LEDGE ROCK SOURCES SUPPLIED COARSE AGGREGATES; LOCAL SAND SOURCES (GENERALLY COLLECTED WITHIN A FEW MILES OF CORRESPONDING LEDGE ROCK SOURCES) SUPPLIED FINE AGGREGATES FOR CONCRETE MIX.



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

AGGREGATE AND TRIAL MIX TESTS
CONCRETE AGGREGATES EVALUATION
PAHROC STUDY AREA, NEVADA

5 JUN 81

TABLE 1

	CONCRETE TRIAL MIX DESIGN CRITERIA								
CONCRETE CONSTITUENTS  AND PROPERTIES	MIX 1 7.5/1.5 !N. <sup>1</sup>		MI 8.5/1.	X 2 5 IN. <sup>1</sup>	MIX 3 8.5/0.75 IN.; SUPER. <sup>1</sup>				
AND PROPERTIES	VOLUME	WEIGHT	VOLUME	WEIGHT	VOLUME	WEIGHT			
CEMENT, NEVADA TYPE II (LOW ALKALI; FT <sup>3</sup> , LBS)	2.87	564	3.25	639	3.25	639			
FLY ASH, WESTERN (REPLACES 20% OF CEMENT BY WEIGHT; FT <sup>3</sup> , LBS)	0.99	141	1.12	160	1.12	160			
SUPERPLASTICIZER (WRDA 19; OZ/CWT) <sup>2</sup>	1 1 1			15					
WATER REDUCER (WRDA 79; OZ/CWT)	5	-	5	_	5				
AIR ENTRAINMENT ADMIXTURE (DARAVAIR: OZ/CWT [FT <sup>3</sup> ])	1.2 [1.08]	-	3.75 [1.08]		3.0 [1.08]	_			
SLUMP, MAXIMUM (INCHES)	3-4		3-4		0-13				
AIR CONTENT, RANGE (PERCENT)	4 - 6		4-6		4 - 6				
WATER/CEMENT RATIO (BY WEIGHT)	0.36		0.32		0.33				
CEMENT FACTOR	7.5		8.5		8.5				

- 1. SACKS OF CEMENT PER CYD / MAXIMUM AGGREGATE SIZE
- 2. OZ/CWT = OUNCES/100 POUNDS OF CEMENT AND FLY ASH
- 3. SLUMP BEFORE ADDITION OF SUPERPLASTICIZER
- 4. SCY = SACKS OF CEMENT/CUBIC YARD OF CONCRETE



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

CONCRETE TRIAL MIX DESIGN CRITERIA PAHROC STUDY AREA, NEVADA

5 JUN 81

TABLE 2

The following tests were performed to evaluate fresh and hardened properties of concrete made from the Pahroc study area aggregates:

# Fresh Properties

- o Unit Weight, Yield and Air Content of Concrete;
- o Slump of Portland Cement Concrete;
- o Air Content of Concrete, Volumetric Method;
- o Making and Curing Concrete Specimens;
- o Making and Testing Accelerated Cure Concrete Compression Test Specimens; and
- o Selecting Proportions for Normal and Heavyweight Concrete.

### Hardened Properties

- o Compressive Strength of Cylindrical Concrete Specimens;
- o Length Change of Hardened Cement Mortar and Concrete;
- o Potential Alkali-Silica Reactivity, Mortar-Bar Method;
- Static Modulus of Elasticity of Concrete in Compression;
- Splitting Tensile Strength of Cylindrical Concrete Specimens;
- o Potential Alkali-Carbonate Rock Reactivity, Length Change Method; and
- o Coefficient of Linear Thermal Expansion of Concrete.

The results of all tests summarized in Table 1 are important to the concrete aggregates evaluation, but hardened concrete properties are considered the most significant (see Section 4.1.1, Requirements for Concrete Aggregates). Although the primary requirement for concrete is a 28-day compressive strength of 6500 psi, one-day (accelerated), seven-day, and 90-day tests were done to determine the range of compressive strength values.

In order to compare different aggregate sources, 28-day compressive strengths of Mix 3 were always used.

Occasionally, fresh concrete properties varied from design concrete specifications and may have affected hardened concrete test results. If known or significant, the causative factor and its effect on test results are mentioned in the discussions on sources of concrete aggregates (Section 4.2.1).

The scope of the study did not allow sample collection and laboratory testing of all potential basin-fill and rock concrete aggregate sources. Existing data and field petrographic and grain-size analyses were used to correlate lithologic and gradation properties to basin-fill units which were not sampled. An important element of this correlation procedure was the use of aerial photography to help delineate the lateral extent of basin-fill deposits. Photogeologic field observations ascertained geomorphological and topographical relationships of basin-fill units and the source rock lithology and distribution of predominantly gravelly materials.

Limited laboratory and field data prevented most correlations of data from tested to untested rock units. Potential aggregate sources were confined to the limits of tested or correlated outcrops as determined from existing data, limited photogeological interpretation, and field reconnaissance.

### 4.1.3 Presentation of Results

Results of the concrete aggregates evaluation are presented in the form of text, tables, figures, 1:62,500 scale drawings,

and appendices. Drawing 1 is a location map showing the position in the study area of all data points used in the Detailed Aggregate Resources Study. All data points are grouped by study type and assigned categorized map numbers (see Section 3.1.3).

Drawing 3 presents the locations of the potential concrete aggregate sources, DARS trenches, select VSARS data stops, and field petrographic and grain-size data stops in the study area. Geologic unit symbols used in Drawing 3 relate to standard geologic nomenclature whenever possible. A conversion table relating these symbols to the geologic unit nomenclature used in other Ertec reports is contained in Appendix Table F-3.

A solid contact line separates basin-fill and rock units in Drawing 3 to differentiate these two basic material types. All rock contacts are taken from published data or limited air-photo interpretation and are dashed. Basin-fill contacts are derived from photogeological mapping with limited field reconnaissance and are also dashed.

Classifications of potential basin-fill and rock concrete aggregate sources are distinguished by different patterns. Patterns for basin-fill and rock sources of the same classification are similar, with the basin-fill pattern emphasized by a dark background tone.

The appendices contain tables that summarize the basic field data collected during the course of the study and the subsequent laboratory test procedures and results. Appendices A and B

contain DARS trench data and petrographic and grain-size data, respectively. Appendix C contains representative trench logs. Appendix Table D-2 presents a laboratory testing flow diagram for the concrete aggregates evaluation. Appendix E presents the chemical analyses of cement, fly ash, and water used in making the concrete trial mixes. Appendix F includes three tables describing soil classification, caliche development, and geologic unit cross reference.

# 4.1.4 Classification of Concrete Aggregates

A classification system was designed to present the most likely basin-fill and crushed-rock concrete aggregate sources. It was developed from an evaluation as well as from an extrapolation of all available data. Data include laboratory test results (compressive strength of concrete and grain-size, abrasion, and soundness of aggregates) and geomorphological and compositional correlations.

The classification system groups potential aggregate sources into three categories:

- Aggregate sources which were used in concrete mixes Class CA1 and Class CA2;
- 2. Aggregate sources which were subjected to basic aggregate tests Class CB; and
- 3. Untested aggregate sources which were correlated to Classes CA1, CA2, or CB Class CC1 and Class CC2.

The classification is presented in hierarchy form; classification of the highest potential source areas is described first, and classification of the lowest potential source areas is described last.

Class

# Explanation

CA1

Basin-fill or rock sources containing aggregates that produced trial mix concrete with 28-day compressive strengths equal to or greater than 6500 psi using Mix 3 (Section 4.1.2).

CA2

Basin-fill or rock sources containing aggregates that produced trial mix concrete with 28-day compressive strengths less than 6500 psi using Mix 3 (Section 4.1.2).

Classes CA1 and CA2 describe those specific sources where basin-fill or crushed-rock aggregates have been collected and used in making trial mix batches of concrete. Following appropriate ASTM standards, concrete cylinders containing the collected aggregates were made, cured, and tested for various hardened concrete properties. The class is divided into two categories by 28-day compressive strength test results.

Generally, aggregates from each potential source area have been tested previously during the VSARS program. Confirmation testing that included gradation, abrasion, and soundness tests was performed when applicable to ensure the continued acceptability of a sample for use in concrete. Abrasion and MgSO<sub>4</sub> soundness values do not exceed coarse aggregate requirements specified in Section 4.1.1. Tested samples of fine aggregate used in the concrete trial mix consistently have MgSO<sub>4</sub> soundness losses exceeding the required 15 percent maximum; however, NaSO<sub>4</sub> soundness losses generally do not exceed 10 percent.

Class

### Explanation

СВ

Basin-fill or rock sources containing aggregates potentially suitable

The same of the sa

for use in concrete; based on acceptable laboratory aggregate test results.

The Class CB describes those source areas that have been sampled and tested only for grain-size gradation, abrasion, and MgSO<sub>4</sub> soundness. Trial concrete mixes were not made. Gradation, abrasion, and soundness values specified in Section 4.1.1 were used to assign this classification to an aggregate source.

Class	Explanation				
CC1	Basin-fill or rock sources containing aggregates potentially suitable for use in concrete; based on correlation with Class CA1 or CA2 areas.				
CC2	Basin-fill sources of aggregates potentially suitable for use in concrete; based on correlation with Class CB areas.				

Untested Class CC deposits are correlated to tested Class CA or CB deposits on the basis of field observations and limited field and laboratory test results. Class CC basin-fill deposits consist of units of the same apparent relative age as Class CA and CB deposits. Class CC1 rock deposits are additional nearby outcrops of the same unit as Class CA deposits.

Field observations and petrographic and grain-size analyses provided correlative data on lithology of adjacent source rock and lithology and general amounts of gravel present in the basin-fill units. Photogeologic interpretations were also used to correlate Class CC basin-fill deposits to Class CA or CB basin-fill deposits. Specific geomorphological parameters correlated during the procedure included surface texture, drainage patterns, relative relief, and topographic profiles.

**E** Ertec

All classifications are based on limited data. Additional field reconnaissance, testing, and case history studies are needed to confirm adequacy, delimit exact areal boundaries, and refine chemical and physical properties.

## 4.2 SOURCES OF CONCRETE AGGREGATES

## 4.2.1 Basin-Fill Sources

Basin-fill sources of concrete aggregates are grouped into four classes, CA1, CB, CC1, and CC2. Deposits defined on the basis of laboratory test data are included in Class CA1 and Class CB. Untested basin-fill deposits correlated to deposits with test data are included in Classes CC1 and CC2.

# 4.2.1.1 Class CA1

There is one Class CA1 basin-fill source identified within the study area. It is located on the western side of northern Pahranagat Valley adjacent to the North Pahranagat Range (Drawing 3).


1. The Class CA1 basin-fill source is an alluvial fan deposit consisting mainly of poorly graded sandy gravel. The gravel ranges from 51 to 74 percent of the deposit (excluding cobbles and boulders), and the sand ranges from 24 to 39 percent. Cobbles and boulders comprise about 10 percent of the total material within the deposit. Silt and clay comprise from three to 11 percent of the deposit.

The gravel clasts sampled are approximately equidimensional to thick-tabular in shape. Approximately 83 percent of the gravel clasts are of satisfactory physical quality; 14 percent are porous, weak, and internally fractured and are of fair quality; and three percent are soft or highly porous and are of poor quality. The collected gravel sample is composed of 86 percent

limestone and dolomitic limestone, nine percent quartzite, and five percent coating material, weathered rhyolite, and chert. About 37 percent of the gravel clasts are partially or completely coated by calcareous material. The dolomite and dolomitic limestone clasts may be susceptible to a deleterious degree to the alkali-carbonate reaction. The rhyolite and chert clasts may be susceptible to a deleterious degree to the alkali-silica reaction.

The sand particles sampled are typically subrounded to angular and are generally similar in composition and quality to the gravel clasts within the deposit. The sand contains approximately 71 percent satisfactory material, 16 percent fair-quality material, and 13 percent poor-quality material. The sand is considered to be susceptible to a deleterious degree to both alkali-carbonate and alkali-silica reactions.

Grain-size gradations of the Class CA1 deposit only partially meet design gradation requirements (Figure 5). The percentages of coarse to medium gravel passing the 2-inch to 0.375-inch sieves is generally deficient. There is an abundance of oversize material that can be processed to provide additional aggregates of all sizes. The percentages of fine aggregates do not conform to design gradation requirements. There is a deficiency of sand passing the No. 8 sieve and an excess of fine sand passing the No. 30 to No. 100 sieve sizes. Processing of the deposit will be necessary to conform to the design gradation requirements. Variations in grain-size gradations will





REQUIRED GRAIN-SIZE DISTRIBUTION ENVELOPES FOR COARSE AND FINE AGGREGATES USED IN CONCRETE (AMERICAN SOCIETY FOR TESTING AND MATERIALS, 1978, C 33; THE RECOMMENDED GRADATIONS FOR AGGREGATES WITH 1.5 AND 0.75 INCH MAXIMUM SIZE ARE COMBINED INTO ONE ENVELOPE).



GRAIN-SIZE DISTRIBUTION ENVELOPES OF BASIN-FILL COARSE AND FINE AGGREGATES POTENTIALLY SUITABLE FOR CONCRETE.



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX

GRAIN-SIZE DISTRIBUTION ENVELOPES CONCRETE AGGREGATES, PA-A- (6-10) PAHROC STUDY AREA, NEVADA

5 JUN 81

FIGURE S

occur within the deposit depending on proximity to the source area. In general, this source is relatively finer grained near the valley axis and coarser grained adjacent to the mountain fronts.

A coarse aggregate sample from the Class CA1 deposit was subjected to laboratory abrasion and MgSO<sub>4</sub> soundness tests and yielded results of 24.5 percent wear and 3.7 percent loss, respectively. These values for abrasion and soundness are well within acceptable ranges for coarse aggregates for concrete-construction-material use. The fine aggregates sample from this deposit was subjected to both MgSO<sub>4</sub> and NaSO<sub>4</sub> soundness tests. The sample failed the MgSO<sub>4</sub> soundness test with a 17.4 percent loss, but passed the NaSO<sub>4</sub> soundness test with a 2.8 percent loss.

Concrete (Mix 3) made using the aggregates from this Class CA1 deposit had a 28-day compressive strength of 7365 psi and a 90-day compressive strength of 8860 psi. Concrete trial Mixes 1 and 2 yielded 28-day compressive strengths of 6065 and 4630 psi, respectively (Table 3). The air content of Mix 2 (11.5 percent) was much higher than the maximum air content as specified by the mix design (6.0 percent) and probably caused a lowering of the compressive strengths of this mix. Fresh concrete properties and hardened concrete test results (chord modulus of elasticity, splitting tensile strength, drying shrinkage) are also included in Table 3. Test results for hardened concrete are generally within or exceed the requirements mentioned in

ATE E1	ATION	CONCRETE MIX DESIGN CRITERIA <sup>2</sup>	F	RESH CO	NCRETE P	ROPERTI												
AGGREGATE SOURCE <sup>1</sup>	FIELD STATION	SACKS OF CEMENT/CYD MAX. AGG. SIZE	SLUMP 3 (IN.)	CONTENT (%)	UNIT WEIGHT (PCF)	WATER/ CEMENT RATIO	CEMENT FACTOR (SCY)	ASTM STANDARD TEST										
								COMPRESSIVE STRENGTH, AS' (PSI)										
	PA-A-	MIX 1	3.75	1.5	149.2	0,36	7.69	CHORD MODULUS OF ELASTICITY, (PSI x 10 <sup>6</sup> )										
	(6-10)	7.5/1.5 IN.																SPLITTING TENSILE STRENGTH, / (PSI)
												DRYING SHRINKAGE, ASTM (PERCENT)						
	<del></del>							COMPRESSIVE STRENGTH, AS										
FILL	PA-A-	MIX 2	4,0	11,5	141.8	0.32	8.28	CHORD MODULUS OF ELASTICITY, (PSI x 10 <sup>6</sup> )										
BASIN-FILL	(6-10)	8.5/1.5 IN.									SPLITTING TENSILE STRENGTH, (PSI)							
									DRYING SHRINKAGE, ASTN (PERCENT)									
								COMPRESSIVE STRENGTH, A										
		MIX 3 8.5/0.75 IN., SUPER- PLASTICIZER	1 8EF. 6 AFT.	6.3	143.4	0.30	8.55	CHORD MODULUS OF ELASTICITY (PSI x 10 6)										
	PA-A- (6-10)							SPLITTING TENSILE STRENGTH (PSI)										
									DRYING SHRINKAGE, AST (PERCENT)									

<sup>1.</sup> BASIN-FILL SOURCES SUPPLIED BOTH COARSE AND FINE AGGREGATES FOR CONCRETE MIX. LEDGE-ROCK SOURCES SUPPLIED COARSE AGGREGATES; LOCAL SAND SOURCES (GENERALLY COLLECTED WITHIN A FEW MILES OF CORRESPONDING LEDGE-ROCK SOURCES) SUPPLIED FINE AGGREGATES FOR CONCRETE MIX.

4. COMPRESSIVE AND TENSILE STRE CYLINDERS. DRYING SHRINKAGE MENS; TIMETABLE INCLUDES A S

<sup>2.</sup> ASTM AND ACI SPECIFICATIONS AND PROCEDURES WERE FOLLOWED IN THE MIX DESIGN AND BATCHING OF THE CONCRETE TRIAL MIXES. THE CONCRETE MIXES CONSISTED OF COARSE AND FINE AGGREGATES, LOW ALKALI CEMENT, FLY ASH ( 20% BY WEIGHT REPLACEMENT OF CEMENT), SUPERPLASTICIZER, AIR-ENTRAINING ADMIXTURE, AND WATER REDUCER.

<sup>3.</sup> BEF. - SLUMP BEFORE ADDITION OF SUPERPLASTICIZER.

AFT. - SLUMP AFTER ADDITION OF SUPERPLASTICIZER.

# HARDENED CONCRETE TEST RESULTS

ASTM STANDARD TEST 4	TIMETABLE							
ASTM STANDARD TEST 4	1 DAY (ACCELERATED	7 DA	7 DAYS		8 DAYS	90 DAYS		
DMPRESSIVE STRENGTH, ASTM C 39 (PSI)	2795	466	4660		6065	6875		
MODULUS OF ELASTICITY, ASTM C 469 (PSI x 10 <sup>6</sup> )	3,20	4.84	4.84		5.21	5.98		
TING TENSILE STRENGTH, ASTM C 496 (PSI)		_	_		490	_		
DRYING SHRINKAGE, ASTM C 157	7 DAYS	14 DAYS	21 DAYS 28 DAYS		35 DAYS			
(PERCENT)	0.00	0.018	0.0	0.029 0.033		0.034		
OMPRESSIVE STRENGTH, ASTM C 39 (PSI)	2090	3920	3920		4630	5580		
D MODULUS OF ELASTICITY, ASTM C 469 (PSI x 10 <sup>6</sup> )	2,18	4.26	4.26		4.44	5.04		
TTING TENSILE STRENGTH, ASTM C 496 (PSI)			_		510	_		
DRYING SHRINKAGE, ASTM C 157	7 DAYS	14 DAYS	14 DAYS 21 C		28 DAYS	35 DAYS		
(PERCENT)	0.00	0.014	0.0	0.025 0.030		0.032		
OMPRESSIVE STRENGTH, ASTM C 39 (PSI)	3300	5750	5750		7365	8860		
O MODULUS OF ELASTICITY, ASTM C 469 (PSI x 10 6)	3.54	4.45	4.45		4.92	5.18		
TTING TENSILE STRENGTH, ASTM C 496 (PSI)			_		615	_		
DRYING SHRINKAGE, ASTM C 157	7 DAYS	14 DAYS	21 0	AYS	28 DAYS	35 DAYS		
(PERCENT)	0.00	0.019	0.031 0.037		0.039			

IPPRESSIVE AND TENSILE STRENGTH VALUES ARE AVERAGES OBTAINED FROM TWO TESTED LINDERS. DRYING SHRINKAGE VALUES ARE AVERAGES OBTAINED FROM TWO TESTED SPECI-NB; TIMETABLE INCLUDES A SEVEN DAY MOIST CURE.



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX

CONCRETE TRIAL MIX TEST RESULTS
PA-A-(6-10)
PAHROC STUDY AREA, NEVADA

5 JUN 1981

TABLE 3

1 OF 1

Section 4.1.1 except initial drying shrinkage values and Mix 2 tensile strength.

The areal extent of the Class CA1 deposit is approximately 3.1  $\rm mi^2$  (8.0  $\rm km^2$ ). It is estimated that the material sampled from this deposit extends to a depth of at least 25 feet (7.6 m). It is also estimated that this deposit has a yield of 65 to 80 percent after handling, poor-quality constituents, and silt and clay losses.

## 4.2.1.2 Class CB

Class CB basin-fill aggregate sources are alluvial fan deposits that have been sampled and laboratory tested and are considered to be potential concrete aggregate sources. Class CB aggregates have not been used in trial concrete mixes. Test results show that these deposits contain at least 30 percent gravel clasts of all sizes (3-inches to No. 4 sieve size), have less than 50 percent abrasion wear, and, where applicable, have less than 18 percent loss when subjected to a MgSO<sub>4</sub> soundness test.

Class CB deposits are located along the west sides of both Pahroc and northern Pahranagat valleys. There are three Class CB sources within the study area and all are alluvial fan (Aaf) deposits.


Class CB basin-fill deposits generally consist of poorly to well-graded, subangular to subrounded sandy gravel. The gravel content of most Class CB deposits ranges from 40 to 74 percent and the silt content ranges from one to five percent. The

deposits are primarily composed of limestone and dolomite, quartzite, and volcanic clasts, with minor caliche and chalcedony.

The gradation of one Class CB deposit approximates the grainsize distribution requirements stated in Section 4.1.1 (Figure
6). The percentages of coarse gravels passing the 2- and 1-inch
sieves are deficient. Sufficient oversize material is available
for crushing to provide additional aggregates of all sizes.
Based on limited data, the percentages of 1-inch to No. 4 coarse
aggregates conform to design gradation requirements. Although
the percentages of fine aggregates conform closely to these requirements, there is a slight deficiency of coarse sand passing
the No. 8 sieve. Variations in grain-size gradations will occur
within the deposit depending on proximity to the source area.
In general, this source is relatively finer grained near the
valley axis and coarser grained adjacent to the mountain fronts.

Laboratory abrasion tests performed on samples from all Class CB deposits resulted in fairly low wear values, ranging from 24.3 to 34.7 percent. Laboratory MgSO<sub>4</sub> soundness test results on coarse aggregate samples ranged from 4.1 to 18.2 percent loss and on fine aggregate samples from 28.2 to 35.3 percent loss. MgSO<sub>4</sub> soundness test results on coarse aggregates were within and exceeded ASTM standards and DARS requirements. MgSO<sub>4</sub> soundness test results on fine aggregates exceeded requirements.

The areal extent of Class CB deposits ranges from 0.25 to 2.8  $\rm mi^2$  (0.65 to 7.2  $\rm km^2$ ). It is estimated that the material



OUVIN-317E IN WITTIME IEU



REQUIRED GRAIN-SIZE DISTRIBUTION ENVELOPES FOR COARSE AND FINE AGGREGATES USED IN CONCRETE (AMERICAN SOCIETY FOR TESTING AND MATERIALS, 1978, C 33; THE RECOMMENDED GRADATIONS FOR AGGREGATES WITH 1.5 AND 0.75 INCH MAXIMUM SIZE ARE COMBINED INTO ONE ENVELOPE).



Grain-size distribution envelopes of Basin-Fill Coarse and fine aggregates potentially suitable for concrete,



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

GRAIN-SIZE DISTRIBUTION ENVELOPES CONCRETE AGGREGATES, CLASS CS PAHROC STUDY AREA, NEVADA

**B JUN 81** 

FIGURE 6

sampled from these deposits extends to a depth of at least 25 feet (7.6 m) and will have a yield of from 70 to 90 percent.

# 4.2.1.3 Class CC1

A Class CC1 source within the study area is located in Pahranagat Valley east of the North Pahranagat Range. This alluvial deposit has been correlated to the adjacent Class CA1 concrete aggregate source on the basis of geomorphological and compositional similarities.

The Class CC1 deposit is therefore considered to be a potential source of concrete aggregates consisting of poorly graded, equidimensional to thick-tabular sandy gravel of generally satisfactory physical quality. The lithology of the gravel is predominantly dolomite and limestone with small amounts of caliche and chert. The areal extent of the Class CC1 deposit is approximately  $2 \text{ mi}^2$  (5.2 km²).

# 4.2.1.4 Class CC2

Class CC2 basin-fill aggregate sources are alluvial deposits that have been correlated to Class CB concrete aggregate sources on the basis of geomorphological and compositional similarities. Class CC2 deposits are therefore assumed to contain material similar in size and composition to Class CB deposits. These four deposits are located along the west side of Pahroc Valley adjacent to the Hiko Range. The areal extent of individual Class CC2 deposits ranges from 0.1 to 3.4 mi<sup>2</sup> (0.3 to 8.8 km<sup>2</sup>).

### 4.2.2 Rock Sources

Rock concrete aggregate sources are grouped into two classes.

Rock defined on the basis of laboratory test data is included in Class CB. Class CC1 contains rocks correlated to tested rock units.

## 4.2.2.1 Class CB

Class CB crushed-rock sources are rock units that have been sampled and laboratory tested and, on the basis of the test results, are considered to be potential sources of concrete aggregates. Class CB rocks have not been used in concrete trial mixes.

The Class CB rock source within the study area is located in Pahroc Valley on the east side of the Hiko Range, north of U.S. Highway 93, and is an intraformational calcareous sandstone of the dolomite rock unit (Do). The sampled interval consists of a limited outcrop of hard, medium-grained, slightly weathered calcareous sandstone.

A laboratory abrasion test performed on this rock yielded a result of 35.5 percent wear. When subjected to a MgSO4 soundness test, the crushed rock exhibited a 3.6 percent loss. These results are well below the maximum allowable abrasion wear of 50 percent and soundness loss of 18 percent for coarse aggregate used as concrete construction material.

# 4.2.2.4 Class CC1

Class CC1 potential concrete aggregate sources are untested rock outcrops of the undifferentiated carbonate rock unit (Cau).

Published geologic maps were used to delineate these outcrops. These sources are part of the same geologic unit as the Class CA1 and CA2 sources in Dry Lake Valley (E-TR-47-DL) and have essentially the same lithologies, limestone, dolomitic limestone, and dolomite.

## 5.0 CONCLUSIONS

Results of the Detailed Aggregate Resources Study indicate that there are sufficient quantities of aggregates available in the Pahroc study area for the construction of the MX missile system.

Good- to high-quality basin-fill and crushed-rock coarse aggregates are present in northern Pahranagat and western Pahroc valleys. Good- to high-quality crushed-rock coarse aggregates are present in the Hiko and North Pahranagat ranges. Sufficient quantities of poor- to satisfactory-quality, fine aggregates are present in basin-fill deposits in the two valleys. After shelter layouts are finalized, potential borrow areas can be delineated based on the results of this study.

Although most rock will supply acceptable coarse aggregates, limited sources are delineated in this study. Sufficient quantities of basin-fill aggregates within the area will probably make processing of crushed-rock aggregates unnecessary.

As discussed in the report, field studies placed an arbitrary cut-off limit of a minimum of 30 percent gravel for the source to be considered for road-base or concrete aggregates. Nevertheless, basin-fill deposits with less than 30 percent gravel are also probably potentially suitable for use as aggregates. However, yield from such sources will be low, and extensive processing and/or blending will be required to satisfy the gradation requirements.

# 5.1 ROAD-BASE AGGREGATES

# 5.1.1 Class RBIa Sources

Four basin-fill deposits consisting of good- to high-quality coarse aggregates acceptable for road base have been located within the study area. They are all alluvial fan units (Aaf) confined to northern Pahranagat and western Pahroc valleys. Their total areal extent is approximately 8.1 mi $^2$  (21 km $^2$ ).

Gradation results indicate that, where sampled, the deposits approximate ASTM standards and DARS requirements. The deposits generally are deficient in coarse and fine gravel, passing the 1.5-inch to No. 4 sieves, and are excessive in fine sand, passing the No.50 to No. 200 sieves. Sufficient oversized material is available for crushing to provide additional aggregates of all sizes.

Abrasion results on tested samples are within ASTM standards and DARS requirements. MgSO<sub>4</sub> soundness results generally are high, just within or exceeding ASTM standards and DARS requirements; where tested, NaSO<sub>4</sub> soundness results are within ASTM standards and DARS requirements.

One good- to high-quality coarse aggregate crushed-rock source acceptable for use as road-base aggregates has been delineated within the study area. This source is a limited outcrop of intraformational calcareous sandstone assigned to the dolomite rock unit (Do). Samples from this rock source yielded test results for abrasion and soundness well within acceptable ranges as specified by ASTM standards and DARS requirements.

# 5.1.2 Class RBIb Sources

Four basin-fill deposits within the study area are defined as potential sources of good- to high-quality aggregates for use as road-base construction material. Geomorphological and compositional similarities were used to correlate these units to tested RBIa deposits. The units are all alluvial fan units (Aaf) confined to northern Pahranagat and western Pahroc valleys. Their total areal extent is approximately 7.4 mi<sup>2</sup> (19.2 m<sup>2</sup>).

### 5.1.3 Class RBII Sources

Several potential road-base aggregate sources defined by limited field and laboratory data are present in various locations throughout the study area. All deposits are alluvial fans, consist predominantly of sandy gravel or gravelly sand, and are compositionally similar to Class RBIa and RBIb deposits. These deposits have a total areal extent of approximately  $10.5 \, \text{mi}^2$   $(27.2 \, \text{km}^2)$ .

### 5.2 CONCRETE AGGREGATES

### 5.2.1 Class CA1 Sources

One basin-fill deposit consisting of good- to high-quality aggregates that produced concrete with 28-day compressive strengths equal to or greater than 6500 psi has been delineated within the study area. Chord modulus of elasticity, splitting tensile strength, and drying shrinkage results generally conform to the standard concrete requirements, although minor deviations do occur.

Gradation results indicate that, where sampled, the deposit approximates ASTM standards and DARS requirements. Typically, percentages of fine gravel conform to gradation specifications, but there is a lack of coarse to medium gravel passing the 2-inch to 0.375-inch sieves. The fine aggregate samples generally contain a deficiency of sand passing the No. 8 sieve and an excess of fine sand passing the No. 30 to No. 100 sieve sizes. Processing of basin-fill deposits can be used to bring gradations within design requirements. Crushing of oversize materials will produce additional aggregates of all sizes. In addition, variations in grain-size gradation will occur within the deposit depending on proximity to the source area. Aggregates are relatively finer grained near the valley axis and coarser grained near the mountain fronts.

Abrasion and soundness tests performed on coarse aggregates from the Class CA1 deposit are also within specified ASTM and DARS requirements. The fine aggregates within these deposits are generally of lower quality (high MgSO<sub>4</sub> soundness losses), but results are inconclusive regarding their use as concrete-construction material. The Class CA1 basin-fill deposit is an alluvial fan unit (Aaf) located in northern Pahranagat Valley. It has a total areal extent of approximately 3.1 mi<sup>2</sup> (6 km<sup>2</sup>).

### 5.2.2 Class CB Sources

Three basin-fill deposits consisting of good- to high-quality coarse aggregates potentially acceptable for use as concrete construction material were delineated within the study area.

These deposits are all alluvial fan units (Aaf) and are confined to northern Paharanagat and western Pahroc valley. Their total areal extent is approximately 5 mi<sup>2</sup> (13 km<sup>2</sup>). No concrete trial mixes were made, but abrasion test results on samples from these deposits were well within acceptable ranges as specified by ASTM standards and DARS requirements. MgSO<sub>4</sub> soundness test results on coarse aggregates were within and exceeded ASTM standards and DARS requirements. MgSO<sub>4</sub> soundness test results on fine aggregates exceeded requirements. The gradation of the Class CB deposit approximates the design grain-size distribution requirements, although, the percentages of coarse gravels passing the 2- and 1-inch sieves are deficient.

# 5.2.3 Class CC1 Sources

One basin-fill alluvial fan deposit (Aaf) in the study area is classified as a potential source of concrete aggregates. The unit was correlated to the Class CA1 source based on geomorphological and compositional similarities. The deposit has a total areal extent of approximately 2 mi $^2$  (5 km $^2$ ).

# 5.2.4 Class CC2 Sources

というなどのできない。

Several alluvial fan units (Aaf) located along the west side of Pahroc Valley are classified as potential sources of concrete aggregates. Units were correlated to Class CB sources on the basis of geomorphological and compositional similarities. They have an areal extent of approximately  $5.4 \, \text{mi}^2$  ( $14 \, \text{km}^2$ ).

### 6.0 RECOMMENDATIONS FOR FUTURE STUDIES

The conclusions of this Detailed Aggregate Resources Study of the Pahroc study area, as enumerated in Section 5.0, are based on limited field and laboratory test results. However, the results presented in this report provide sufficient data for selecting potential borrow areas. After selection of the borrow areas, more extensive studies are required to further determine the characteristics of the aggregates.

### 6.1 SOURCES OF ROAD-BASE AGGREGATES

It is recommended that additional field exploration (backhoe or drilling) and detailed laboratory testing be performed. The laboratory tests should consist of sieve analysis, resistance to abrasion, CBR, and other appropriate tests as deemed necessary by the designers.

### 6.2 SOURCES OF CONCRETE AGGREGATES

It is recommended that additional field investigations (backhoe or drilling) and detailed laboratory testing be performed. The aggregate samples should be subjected to the following tests:

- o Sieve Analysis;
- o Resistance to Abrasion;
- o Soundness;
- o Specific Gravity and Absorption; and
- Petrographic Examination of Aggregates for Concrete.

In addition, the following detailed tests using concrete made from these aggregates should be performed:

- o Compressive Strength;
- Splitting Tensile Strength;
- o Flexural Strength;
- o Shrinkage;

- o Thermal Expansion;
- o Modulus of Elasticity;
- o Potential Alkali-Silica Reactivity;
- o Potential Alkali-Carbonate Rock Reactivity; and
- o Resistance of Concrete to Rapid Freezing and Thawing.

In addition, it is recommended that concrete trial mixes with different size aggregates and admixtures be made in order to assess the variation in compressive strength, durability, shrinkage, and thermal properties of concrete.

In-progress Verification studies (E-TR-27-PA-I and II) performed in Pahroc Valley indicate that potential for sulfate attack of soils on concrete is "negligible." However, it is recommended that additional studies be made to further evaluate the potential for sulfate attack of soils on concrete and to determine the type of cement to be used in concrete.

# 7.0 BIBLIOGRAPHY

- American Concrete Association, 1975, Durability of concrete: American Concrete Institute Publication, SP-47, 385 p.
- American Concrete Institute, 1977, Recommended practice for selecting proportions for normal and heavyweight concrete: American Concrete Institute, 20 p.
- Concrete Institute Publication, SP19, 50 p.
- American Public Works Association, 1970, Standard specifications for public works construction: Part 2 Construction Materials, Sec. 200 Rock Materials, p. 62-70.
- American Society for Testing and Materials, 1975, Significance of tests and properties of concrete and concrete-making materials: American Society for Testing and Materials, Special Technical Publication No. 169-A, 571 p.
- \_\_\_\_\_\_, 1978, Annual book of ASTM standards, Part 14; concrete and mineral aggregates: American Society for Testing and Materials, Part 14, 814 p.
- , 1979, Annual book of ASTM standards, Concrete and Mineral Aggregates, American Society of Testing and Materials, Part 14, 826 p.
- Bates, R. L., 1969, Geology of the industrial rocks and minerals: Dover Publications, Inc., New York, 459 p.
- Blanks, R., and Kennedy, H., 1955, The technology of cement and concrete, v. 1: John Wiley & Sons, Inc., 422 p.
- Borup, H. J., and Bagley, D. G., 1976, Soil survey of Meadow Valley area, Nevada-Utah, parts of Lincoln County, Nevada, and Iron County, Utah: U.S. Department of Agriculture, Soil Conservation Service, 174 p.
- Brown, L., 1959, Petrography of cement and concrete: Portland Cement Research Department, Bulletin 111.
- Carr, W. J., 1966, Geology and test potential of Timber Mountain Caldera area, Nevada: U.S. Geological Survey, Technical Letter NTS-174.
- Erlin, B., 1966, Methods used in petrographic studies of concrete: Portland Cement Association, Research Department Bulletin 193, 17 p.
- Ertec Western, Inc., 1981, Verification study, Pahroc Valley, Nevada: Cons. Report for BMO, v. I and II, (FN-TR-27-PA), (in progress).

- Freedman, S., 1971, High strength concrete: Portland Cement Association, Concrete Information Reprint, 17 p.
- Fugro National, Inc., 1978, Aggregate resources report, Department of Defense and Bureau of Land Mangement lands, southwestern United States: Cons. Report for SAMSO, (FN-TR-20-D) 85 p.
- Lake Valley, Muleshoe Valley, Delamar Valley, Pahroc Valley, Nevada: Cons. Report for BMO, (FN-TR-37-a) 45 p.
- Gile, L. H., 1961, A classification of Ca horizons in soils in a desert region, Dona Ana County, New Mexico: Soil Science Society America Procedures, v. 25, No. 1, p. 52-61.
- Gile, L. G., Peterson, F. F., and Grossman, R. B., 1965, The K horizon of carbonate accumulation: Soil Science Society v. 99, p. 74-82.
- Hadley, D. W., 1961, Alkali reactivity of carbonate rocksexpansion and dedolomitization: Research and Development Laboratories of the Portland Cement Association, Bulletin 139, p. 462-474.
- rocks: Research and Development Laboratories of the Portland Cement Association, Bull. 176, 19 p.
- vity of sand-gravel aggregates: Research and Development Laboratories of the Portland Cement Association, Bulletin 221, p. 17-33.
- Hose, R. K., Blake, M. C., Jr., and Smith, R., 1976, Geology and mineral resources of White Pine County, Nevada: Nevada Bureau of Mines and Geology, Bulletin 85, 105 p.
- Howard, E. L., compiler, 1978, Geologic map of the eastern Great Basin, Nevada and Utah: Terra Scan Group LTD., 3 sheets.
- Ketner, K. B., 1976, Map showing high-purity quartzite in California, Nevada, Utah, Idaho, and Montana: U.S. Geological Survey Map, MF-821.
- Lerch, W., 1959, A cement-aggregate reaction that occurs with certain sand-gravel aggregates: Research and Development Laboratories of the Portland Cement Association, Bulletin 122, p. 42-50.
- McKee, E. D., and Weir, G. W., 1953, Terminology for stratification and cross-stratification in sedimentary rocks: Geological Society America Bulletin, v. 64, p. 381-389.

- Mielenz, R. C., 1980, Proposed test method for length-change of concrete due to alkali-carbonate rock reaction: Richard C. Mielenz, P. E., Inc., Materials and Petrography, Gates Mills, Ohio.
- National Ready Mixed Concrete Association, 1961, Selection and use of aggregate for concrete: National Ready Mixed Concrete Association, Publication No. 101, p. 513 542.
- National Sand & Gravel Association, 1977, Compilation of ASTM standards relating to sand, gravel and concrete: NSGA Circular No. 113, NRMCA Publication No. 137.
- Nevada State Department of Highways, 1976, Standard specifications for road and bridge construction: State of Nevada Department of Highways, Section 704, p 819-822.
- , No date, Materials and research laboratory, aggregate test data: Unpublished.
- Office of State Inspector of Mines, 1977, Directory of Nevada mine operations active during calander year 1976: Nevada Industrial Commission, 59 p.
- Papke, G. K., 1973, Industrial mineral deposits of Nevada: Nevada Bureau of Mines and Geology, map 46.
- Pickett, G., 1956, Effect of aggregate on shrinkage of concrete and hypothesis concerning shrinkage: Portland Cement Association, Research Department, Bulletin 66, 5 p.
- Steinour, H. H., 1960, Concrete mix water-how impure can it be? Research and Development Laboratories of the Portland Cement Association, Bulletin 119, p. 33-50.
- Stewart, H., and Carlson, J. E., 1978, Geologic Map of Nevada: U.S. Geological Survey, scale 1:500,000.
- Travis, R. B., 1955, Classification of rocks: Quarterly of the Colorado School of Mines, v. 50, No. 1, 98 p.
- Tschantz, C. M., and Pampeyan, E. H., 1970, Geology and mineral deposits of Lincoln County, Nevada: Nevada Bureau of Mines, MacKay School of Mines, University of Nevada, Bulletin 73, 188 p.
- U. S. Army Corps of Engineers, 1953, Test data, concrete aggregate in continental U.S.: U. S. Army Corps of Engineers v. 1, areas 2 and 3.
- U. S. Army Corps of Engineers, 1977, Handbook for concrete and cement, method of test for coefficient of linear thermal expansion of concrete: Waterways Experiment Station, Vicksburg, Mississippi and U. S. Army Corps of Engineers, CRD-C39-55, Part I, 2 p.

- U. S. Department of the Interior, 1966, Concrete Manual; A Manual for the Control of Concrete Construction: U. S. Department of the Interior, Bureau of Reclamation, 642 p.
- , 1974a, The mineral industry of Nevada: U.S. Department of the Interior, Bureau of Mines.
- rior, Bureau of Reclamation, 810 p.
- , 1975a, Concrete Manual: Water Resources Technical Publication, 627 p.
- , 1975b, Concrete Manual: U. S. Department of the Interior, Bureau of Reclamation, 627 p.
- \_\_\_\_\_, Lower Colorado Regional Office, Nevada Aggregate Data, Unpublished.
- U. S. Geological Survey, 1964, Mineral and water resources of Nevada: U. S. Government Printing Office, Washington, D.C., 314 p.
- Voskuil, W. H., 1966, Selected readings in mineral economics: Nevada Bureau of Mines, Report 12, 18 p.
- Waddell, J., 1976, Concrete inspection manual: International Conference of Building Officials, 332 p.
- Womack, J. C., et al., 1963, Materials manual: California Highway Transporation Agency, v. I and II.

# PERSONAL COMMUNICATION

Polivka, Milos, 1981, Consulting Civil Engineer, Berkeley, California.

# APPENDIX A

SUMMARY OF FIELD AND LABORATORY TEST DATA

# FIELD AND LABORATORY TEST DATA

Field observations and laboratory test data on samples collected at selected stations are presented in Table A-1. Field stations were established at various locations throughout the study area where detailed descriptions of potential basin-fill, fine aggregate, and crushed-rock sources were recorded. Detailed explanations for the column headings of Table A-1 are as follows:

CO	LU	MN	HEA	<b>\DING</b>	

### **EXPLANATION**

MAP NUMBER	Map numbers are sequentially arranged
	identifiers of field stations occupied
	during the course of the aggregate

study.

FIELD STATION These designations are internal DARS identifiers of all field stations. Each one consists of a two-letter valley abbreviation followed by the letter A

(aggregate trench).

LOCATION The location column lists the geographic portion of the valley in which the field station is located (e.g., NE-northeast).

GEOLOGIC UNIT The geologic unit listed is a term used to differentiate basin-fill deposits based on geomorphology. A geologic unit cross reference, outlining all units used, is included as Table F-3.

Material descriptions are based on either field or laboratory USCS classifications using appropriate ASTM standards for basin-fill deposits. Coarse and fine aggregate gradations used in concrete trial mix designs are included at the end of each concrete aggregate

trench group.

Appropriate field or laboratory ASTM standards are used to classify sampled material. The Unified Soil Classification System is used in this study. Table F-1 contains detailed information on the USCS.

MATERIAL DESCRIPTION

USCS SYMBOL

### FIELD OBSERVATIONS

# Boulders and/or Cobbles

The estimated occurrence of boulders and cobbles is based on an appraisal of the entire deposit. Cobbles have an intermediate diameter of 3 to 12 inches (8 to 30 cm); boulders have an intermediate diameter of 12 inches (30 cm) or more. Because of sample-size limitations, boulders were not generally sampled. Cobbles were representatively sampled for concrete aggregate evaluations but only generally sampled for road-base aggregate evaluations. Field observations of boulders and cobbles are important considerations for in-situ gradations only. Number percentages are equated to the following equivalent dry weight terms:

> Rare - 1 - 4 percent Few - 5 - 20 percent Some - > 20 percent

# Gravel

Coarse aggregate particles that pass a 3-inch (76-mm) sieve but are predominantly retained on a No. 4 (4.75 mm) sieve.

# Sand

Fine aggregate particles that almost entirely pass a No. 4 sieve but are predominantly retained on a No. 200 (0.075 mm) sieve.

# Fines

Soil particles that pass a No. 200 sieve (silt and clay).

# Overburden Thickness (Feet)

Surficial soil overlying a usable aggregate deposit. Material generally consists of silt and sand with low concentrations of gravel. Numbers presented indicate thickness of deposit in feet.

# Total Trench Depth (Feet)

Depth, in feet, of trench excavation used to collect aggregate samples. Depth followed by the letter R indicates that depth below which soil strength exceeded excavation capability. The common conditions for refusal (R) are calcium carbonate accumulation (caliche) and/or presence of oversized material.

Deleterious
Materials
(Material/Depth/
Stage)

Deleterious materials are substances that are potentially detrimental to concrete in service. Substances that may be present include: organic impurities, low density materials (ash, vesicles, pumice, cinders), amorphous silica (opal, chert, chalcedony), volcanic glass, caliche and clay coatings, mica, gypsum, pyrite, chlorite, friable materials, and aggregates that may react chemically or be affected chemically by other external influences. The most common deleterious material is calcium carbonate accumulation (caliche). When it is abundant, the interval(s) at which it occurs and the stage of development (Table F-2) are listed. Caliche can occur disseminated throughout a deposit, as lenses, and as discrete layers. The depth space is left blank when caliche is present throughout the deposit.

# Plasticity (Index)

Plasticity index (PI) is the range of water content, expressed as a percentage of the weight of the oven-dried soil (less than No. 40 sieve material), through which a soil behaves plastically. It is defined as the liquid limit minus the plastic limit. Field terms used to approximate plasticity index range include the following.

# Plasticity PI

# Wet Consistency

Slight (4-15)

Slightly sticky; after pressure, soil adheres to both thumb and finger but comes off cleanly. Does not appreciably stretch.

Medium (15-30)

Sticky; after pressure, soil adheres to both thumb and finger and tends to stretch somewhat before pulling apart from either digit.

High (>30)

Very sticky; after pressure, soil adheres strongly to both digits and is markedly stretched when digits are separated.

# Hardness

Hardness determination is a field test used to identify materials that are soft or poorly bonded by estimating their resistance to crushing by impact with a rock hammer. Classification terms used include:

Soft

Hammer point indents deeply with firm blow.

Moderately Hard

Hammer point indents only shallowly with

firm blow.

Hard

Hammer breaks hand-held sample with one firm blow.

Very Hard

Hammer breaks intact sample with many blows.

Weathering

Weathering is defined as any changes in color, texture, strength, chemical composition, or other properties of rock due to the effects of various atmospher-Field terms used to ic conditions. classify degree of weathering include: fresh, slight(ly), moderate(ly), or very weathered.

### LABORATORY TEST DATA

Sieve Analysis (ASTM C 136)

A sieve analysis is the determination of the proportions of particles existing within certain size ranges in granular material by separation on sieves of different size openings, expressed as a weight percent of the total sample. Numbers presented represent the percent of the sample passing through the stated Sieve sizes include: sieve size. 3-inch (75-mm), 2 1/2-inch (63-mm), 2-inch (50-mm),  $1 \frac{1}{2}-inch (38.1-mm)$ , 1-inch (25-mm), 3/4-inch (19-mm), 1/2-inch (12.5-mm), 3/8-inch (9.5-mm), No. 4 (4.75-mm), No. 8 (2.36-mm) No. 16 (1.18-mm) No. 30 (0.6-mm), No. 50 (0.3-mm), No. 100 (0.15-mm), No. 200 (0.075-mm).

Specific Gravity and Absorption

In general, specific gravity is defined as the ratio of the weight in air of a (ASTM C 127 and 128) unit volume of material to the weight in air of an equal volume of water. Absorption is the process by which a liquid is drawn into and tends to fill permeable pores in a porous solid body, also, the increase in weight of a porous

solid body resulting from the penetration of a liquid into its permeable pores. Specific definitions of bulk, bulk saturate-surface-dry (SSD), and apparent specific gravity, as well as absorption are contained in ASTM-E 12-70 and C 125, respectively.

# Fineness Modulus

Fineness modulus is an empirical factor obtained by adding the total percentages of a sample of aggregate, retained on each of a specified series of sieves, and dividing the sum by 100.

# Unit Weight

Unit weight is the weight of a unit volume of dry, rodded aggregate, commonly expressed as pounds per cubic foot (pcf).

# Abrasion Test (ASTM C 131)

The abrasion test is a method for testing resistance to wearing away by rubbing and friction, by placing a specified quantity of aggregates in a steel drum (the Los Angeles testing machine), rotating the drum 500 times, and determining the percent of material worn away.

# Soundness Test (ASTM C 88)

Soundness tests are used to determine resistance to large or permanent volume changes of aggregates by placing samples in saturated solutions of magnesium or sodium sulfate. The test furnishes information useful in studying resistance to weathering action, particularly when adequate service records of the material tested are not available. For concrete aggregate tests, magnesium sulfate soundness tests are run first. If the material fails this test, sodium sulfate soundness tests are performed.

# Petrographic Examination (ASTM C 295)

A petrographic examination is a procedure used to identify the physical and chemical properties of aggregates that have a bearing on the quality of the material in consideration of its intended use. Typical properties analyzed include: description and classification of constituents, relative amounts of constituents, particle coatings, rock type, particle condition

and particle shape, texture and structure, color, mineral composition and heterogeneities, and presence of constituents known to cause deleterious chemical reactions in concrete.

# Alkali Reactivity

# Alkali-Silica ASTM C 227

A potential alkali-silica reactivity test evaluates the susceptibility of cement-aggregate combinations to expansive reactions involving the alkalies sodium and potassium by measurement of the increase (or decrease) in length of mortar bars containing the combination during storage under prescribed conditions of test.

# Alkali-Carbonate ASTM Proposed Standard

A potential alkali-carbonate reactivity test evaluates the susceptibility of cement-aggregate combinations to expansive reactions involving the carbonates of dolomite (in certain calcitic dolomites and dolomitic limestones) by measurement of the increase (or decrease) in length of concrete specimens (prisms) containing the combination during storage under prescribed conditions of test. This test is a proposed ASTM standard and has not been formally approved by the American Society of Testing and Materials.

## AGGREGATE USE CLASSIFICATION

# Road Base Aggregate

RBIa

Basin-fill or rock sources containing materials suitable for use as road-base aggregates; based on acceptable laboratory aggregate test results.

RBIb Basin-fill sources containing materials suitable for use as road-base aggregates; based on correlation with Class RBIa areas.

RB II Potential basin-fill sources of materials suitable for use as road-base aggregates; based on photogeologic interpretations, field observations, and limited or inconclusive sieve analysis and/or abrasion data.

Concrete Aggregate	CA1	Basin-fill or rock sources containing aggregates that produced trial mix concrete with 28-day compressive strengths equal to or greater than 6500 psi.
	CA2	Basin-fill or rock sources containing aggregates that produced trial mix concrete with 28-day compressive strengths less than 6500 psi.
	СВ	Basin-fill or rock sources containing aggregates potentially suitable for use in concrete; based on acceptable laboratory aggregate test results.
	CC1	Basin-fill or rock sources containing aggregates potentially suitable for use in concrete; based on correlation with Class CA1 or CA2 source areas.
	CC2	Basin-fill sources containing aggregates potentially suitable for use in concrete; based on correlation with Class CB source areas.
	FA	Basin-fill sources containing fine aggregates used with crushed-rock samples for certain concrete trial mixes.

			,							_
8ER	FIELD		GEOLOGIC	MATERIAL	USCS	AND/ .ES	MATE	RIBUTION COB	FINER	3
MAP NUMBER	STATION	LOCATION	UNIT	DESCRIPTION	SYMBOL	BOULDERS AND	GRAVEL (3)	SAND	FINES	
201	PA-A-1	Pahroc Valley, W	Aaf	Sandy Gravel	GW	Some/ Rare				1
202	PA-A-2	Pahroc Valley, W	Aaf	Sandy Gravel	G₩	-/Few	! ! !			1
203	PA-A-3	Pahroc Valley, W	Aaf	Sandy Gravel	GP-GM					1
	PA-A-(1,2)			Sandy Gravel	GW-GM					
204	PA-A-4	Pahroc Valley, NW	Aaf	Sandy Gravel	GM	-/Rare	50	35	15	
205	PA-A-5	Pahroc Valley, NW	Aaf	Sandy Gravel	GM	~/Few	50	35	15	
206	PA-A-6	Pahranagat Valley	Aaf	Sandy Gravel	GW-GM	Some/ Rare				
207	PA-A-7	Pahranagat Valley	Aaf	Sandy Gravel	GW-GM	-/Some		,		, , , , , , , , , , , , , , , , , , , ,
208	PA-A-8	Pahranagat Valley	Aaf	Sandy Gravel	GW	-/Some				
209	PA-A-9	Pahranagat Valley	Aaf	Sandy Gravel	GP	Rare/ Some				
210	PA-A-10	Pahranagat Valley	Aaf	Sandy Gravel	GP-GM	Same/ Few				
	PA-A-(6, 7,8,9,10)			1.5in-0.75in						
	PA-A-(6, 7,8,9,10)			0.75in-No.4						
	1	i	1	}						

											_	
	FIELD	OBSERVATIONS										
OVERBURDEN THICKNESS (FEET)	TOTAL TRENCH DEPTH (FEET; R=	DELETERIOUS MATERIALS	PLASTICITY	NESS	WEATHERING	SIEVE AN						IS,
OVER THIC	REFUSAL DEPTH)	(MATERIAL/DEPTHS/ STAGE)	PLAST	HARDNESS	WEAT	3 IN.	2½ IN.	2 IN.	1½ IN.	1 IN.	<sup>3</sup> / <sub>4</sub> IN.	
1.5	8.5(R)	Caliche/3-4/II	Slight			96.9	95.3	94.1	89.3	78.7	70.4	6
1.5	12.0	Caliche/1.5-2.5, 9-10/II	Slight			100	93.5	92.5	<b>87.</b> 3	76.5	70.1	•
1.0	4.0(R)	Caliche/1-1.5,4/II										
						100	94.1	91.5	85.6	78.3	71.6	•
1.0	10.0(R)	Caliche/1-2,10/II										
2.0	6.5(R)	Caliche/2-6.5/II										
1.0	13.2	Caliche Rare/-/II	Slight			100	96.5	94.6	93.2	85.0	80.0	1
1.0	12.8	Caliche Rare/-/I	Slight		}	100	98.5	95.5	92.3	85.7	79.0	
1.5	12.8	Caliche Rare/-/I,II	Slight					100	96.7	87.2	78.3	
1.0	13.0	Chert, Caliche/-/I	Slight			85.9	85.9	82.8	78.5	67.8	61.5	
0.5	13.5	Chert;Phyllite	Slight			83.5	81.4	67.0	64.7	52.0	44.7	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
			 						100	55.3	1.1	
									]   		100	

# LABORATORY TEST DATA

												AS	<u>TM C 12</u>	7 AND A	128			1
LYSI	S, AST	M C 136	(PERC	ENT PA	assing	i)				СО	ARSE A	GGREGA		F	INE AG	GREGAT		
L	<del></del>	<del></del>		<del></del>	<del></del>		,	<del></del>	<del></del>	SPEC	FIC GR	AVITY	F.	SPECI	FIC GR	AVITY	P. (T.V.)	, 1
9/4 IN.	½ IN.	<sup>3</sup> /8 IN.	NO. 4	NO. 8	NO. 16	NO. 30	NO. 50	NO. 100	NO. 200	BULK	BULK SSD	APPAR- ENT	ABSORP. (PERCENT)	BULK	BULK SSD	APPAR- ENT	ABSORP. (PERCENT)	
0.4	62.2	55.7	43.7	33.9	25.6	18.3	9.7	3.6	0.5									
0.1	62.3	56.8	45.9	36.3	27.7	19.4	13.7	4.5	1.0									
71.6	64.5	59.6	49.6	40.0	30.9	22.7	14.2	8.3	5.3									
80.0 79.0	71.0			39.0	31.3	25.9	19.8	14.6	10.2									
78.3	64.5		36.2	25.2	19.2	16.0	12.5	9.1	4.4									
61.5	50.7	43.2	30.9	23.4	18.7	15.7	11.5	7.3	4.3									
44.7	37.2	33.3	26.5	23.1	20.2	17.7	14.3	10.4	6.1									
1.1										2.64	2.66	2.69	0.67					
00	72	50	3							2.61	2.66	2.73	1.7					

ŀ											
			ABRASION TEST	SOL	INDNESS T (PERCE)	EST, ASTM NT LOSS)	C 88	PETROGRAPHIC	ALKALI R	EACTIVITY	E USE
	FINENESS MODULUS (PERCENT)	UNIT WEIGHT (PCF)	ASTM C 131 (PERCENT	COA AGGRI	RSE EGATE	FI AGGR	NE EGATE	EXAMINATION ASTM C 295	SILICA METHOD, ASTM C 227	CARBONATE METHOD, PROP. ASTM	AGGREGATE USE
			WEAR)	MgSO4	NaSO4	MgSO4	NaSO4		METHOD, ASTM C 227 (LENGTH CHANGE, PERCENT)	METHOD, PROP. ASTM (LENGTH CHANGE, PERCENT)	AGGF CLAS
											RBIa,C
											RBIa,C
											RBIa,C
ومتنافضيتهم			35.5	13.0		28.2					
in area and a						i :					RBIb,C
مريست يستدريفان											RBIb,
											RBIa,
											RBIa,
					; 1 2						RBIa,
					;						RBIa,
					9 : :						RBIa
								Performed			
		100						Performed			



SUMMARY OF FIELD A TEST DA PAHROC VALLE

5 JUN 81

TABLE A

		sou		EST, ASTM	C 88		ALVALIB	EACTIVITY	SE
<b>T</b> WEIGHT	ABRASION TEST	604	<del></del> -	(T LOSS)		PETROGRAPHIC			TE U
T WEIGHT (PCF)	ASTM C 131 (PERCENT	COA AGGRE	EGATE	AGGR	NE EGATE	EXAMINATION ASTM C 295	SILICA METHOD, ASTM C 227	CARBONATE METHOD, PROP. ASTM	EGA
	WEAR)	MgSO4	NaS <b>O</b> 4	MgSO4	NaSO4		(LENGTH CHANGE, PERCENT)	PROP. ASTM (LENGTH CHANGE, PERCENT)	AGGREGATE USE CLASSIFICATION
									RBIa,CB
!									RBIa,CB
									RBIa,CB
	35.5	13.0		28.2					
									RBIb,CC2
									RBIb,CC2
									RBIa,CA
								{ } }	RBIa,CA
		; ! !							RBIa,CA
		;							RBIa,CA
		: !							RBIa,CA
					i	Performed			
100						Performed			



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

SUMMARY OF FIELD AND LABORATORY
TEST DATA
PAHROC VALLEY, NEVADA

5 JUN 81

TABLE A-1

PAGE 1 OF 2

MAP NUMBER	FIELD STATION	LOCATION	GEOLOGIC UNIT	MATERIAL DESCRIPTION	USCS SYMBOL	BOULDERS AND/ OR COBBLES	GRAVEL BAHT BAHT BAHT BAHT BAHT BAHT BAHT BAHT	RIBUTION COBINERCEN CO	ON OF FINER BLES T)	OVERBURDEN
	PA-A-(6, 7,8,9,10) PA-A-(6, 7,8,9,10)			Blend(1.5in-No.4) No.4-No.200						

<b>}</b>												_
	FIELD	OBSERVATIONS										
OVERBURDEN THICKNESS (FEET)	TOTAL TRENCH DEPTH (FEET; R=	DELETERIOUS MATERIALS	PLASTICITY	NESS	WEATHERING		·	<del>,</del>	SI	EVE A	NALYS	ıs,
OVERI THIC	REFUSAL DEPTH)	(MATERIAL/DEPTHS/ STAGE)	PLAST	HARDNESS	WEAT	3 IN.	2½ IN.	2 IN.	1½ IN.	1 IN.	<sup>3</sup> / <sub>4</sub> IN.	
									100	78	51	(1) The second of the second o

	1 4	2ORA	TORY	TEST	DATA
--	-----	------	------	------	------

T2A 21	M C 13	6 (PERC	PENT D	ASSING							AS	<u>TM C 12</u>	AND A	128	ION,		
113, A31	W C 13	OIFER	JENI P	MOSING	) )					IFIC GR	GGREGA			FIC GR			FIN
1/ <sub>2</sub> IN.	<sup>3</sup> / <sub>8</sub> IN.	NO.	NO.	NO. 16	NO. 30	NO. 50	NO. 100	NO. 200	BULK	<u> </u>	APPAR- ENT	ABSORP. (PERCENT)	BULK	BULK SSD	APPAR- ENT	ABSORP. (PERCENT)	(PE
36	25	2															
		100	79.0	60.8	46.8	29.0	13.0	3.5					2.56	2.61	2.70	2.1	
														<u>{</u> 			
														<b>!</b> :			
													<u> </u>				
				†   			} } }						[   	}			
											}						
											}						
	; ; ;																
	{	{	{														

INENESS		ABRASION TEST		(PERCEN	EST, ASTM IT LOSS)	C 88	PETROGRAPHIC		EACTIVITY	AGGREGATE USE CLASSIFICATION
ODULUS PERCENT)	UNIT WEIGHT (PCF)	ASTM C 131 (PERCENT	COA AGGRI	RSE GATE	AGGR	NE EGATE	EXAMINATION ASTM C 295	SILICA METHOD, ASTM C 227 (LENGTH	CARBONATE METHOD, PROP. ASTM	
		WEAR)	MgSO4	NaSO4	MgSO4	NaSO4		(LENGTH CHANGE, PERCENT)	(LENGTH CHANGE, PERCENT)	
	104.0	24.5	3.7				·			
2.71					17.4	2.9	Performed			
					1					
				)    -						
				i !						
	}					}				1



MX SITING DEPARTMENT BMC

SUMMARY OF FIELD AND TEST DATA PAHROC VALLEY, N

5 JUN 81

TABLE A-1

	ABRASION TEST	l	(PERCEI	EST, ASTM NT LOSS)	C 88	PETROGRAPHIC	ALKALI R	: USE TION	
WEIGHT (PCF)	ASTM C 131 (PERCENT	CO/ AGGR	ARSE EGATE	AGGR	NE EGATE	EXAMINATION ASTM C 295	CILICA	CARBONATE METHOD, PROP. ASTM	AGGREGATE USE CLASSIFICATION
	WEAR)	MgSO4	NaSO4	MgSO4	NaSO4		METHOD, ASTM C 227 (LENGTH CHANGE, PERCENT)	PROP. ASTM (LENGTH CHANGE, PERCENT)	AGGR
4.0	24.5	3.7							
				17.4	2.9	Performed			
		!							
		!							
		, i							
		, ,							
				}					



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

SUMMARY OF FIELD AND LABORATORY TEST DATA PAHROC VALLEY, NEVADA

5 JUN 81

TABLE A-1

Page 2 of 2



# APPENDIX B

SUMMARY OF FIELD PETROGRAPHIC AND GRAIN-SIZE ANALYSES

# FIELD PETROGRAPHIC AND GRAIN-SIZE ANALYSES

Field petrographic observations are presented in Table B-1. Field stations were established at various locations throughout the study area where detailed petrographic descriptions of potential basin-fill sources of aggregates were recorded. Detailed explanations for the column headings of Table B-1 are as follows:

COLUMN HEADING	EXPLANATION
MAP NUMBER	Map numbers are sequentially arranged identifiers of field petrographic stations occupied during the course of the aggregate study.
FIELD STATION	These designations are internal DARS identifiers of field patrographic designations.
LOCATION	The location column lists the geographic portion of the valley in which the field station is located (e.g., NE-northeast).
GEOLOGIC UNIT	The geologic unit listed is a term used to differentiate basin-fill deposits based on geomorphology. A geologic unit cross reference, outlining all units used, is included as Table F-3.

# FIELD OBSERVATIONS

Clast Count	Clast or petrographic counts are the main data collected during the field petrographic analysis. Data collected include lithology and percent present by size. Categorization by lithology is done to determine general percentages of nondeleterious and deleterious materials.
	rials.

# Other Deleterious Clasts Present additional types of materials present that are of poor quality for use as aggregate. Items mentioned include samples of rock types not sieved, counted, and described under clast count, such as: amorphous silica

(chert, opal, chalcedony), volcanic glass, mica, chlorite, friable materials, low density clasts (ash, vesicles, pumice, cinders), gypsum, pyrite, organic material, and coatings (clay and caliche).

# Size Distribution

The estimated occurrence of boulders and cobbles is based on the appraisal of an entire deposit only if the materials are observed in the banks of prominent stream channels. Size distribution information for gravel was generally recorded only at trench locations. Any gravel values given are expressed as a percent of the total amount of less than 3.0-inch material present. The numeral zero is used to indicate a size fraction not observed, and the letter R is used to indicate the rare occurrence of a size fraction (one to four percent).

# Gradation

Gradation information was recorded at trench locations only.

# Maximum Particle Size

Maximum particle size is defined as the intermediate diameter length of the most frequently occurring clast present in a deposit (in centimeters). Erratic oversized materials (boulders, large cobbles) are generally not represented as the maximum particle size.

# Particle Shape

Shape of clasts are classified into the following six categories.

Angular (ANG)

Particles have sharp edges and relatively plane sides with unpolished surfaces.

Sub-angular (SA)

Particles are similar to angular but have somewhat rounded edges.

Sub-rounded (SR)

Particles exhibit nearly plane sides but have well-rounded corners and edges.

Rounded (R)

Particles have smoothly curved sides and no edges.

Platey (P)


Particles are thin and flat with either rounded or nonrounded corners and edges.

Elongate (E)

Particles are several times longer than they are wide with rounded corners and edges.

# Remarks

This column is used to describe the general site location of petrographic field stations; location terms used include: surface, shallow wash, stream channel bank or bottom, borrow pit, and road cut. Surface indicates analysis was performed on top of the stated geologic unit. Shallow wash indicates analysis was performed on top of the unit but at the bottom of a small swale. Stream channel bank or bottom indicates analysis was performed in an exposed section (incision) or within a minor stream channel deposit, respectively.



# 20F

E-TF

1)


#}

43

1,

...

# AD-A112688



S 3 IN. BIAMETEI  DE  Vb CALI-CHER	CHE CHEN		6			2	2
	70	4					
N-DELE		12	28	20	12	4	8
		46	48	80	88	94	76
Qtz		34	12				8
GEOLOGIC UNIT		Aaf	Aaf	Aaf	Aaf	Aaf	Aaf
LOCATION		Pahroc Valley, C	Pahroc Valley, C	Pahroc Valley, N	Pahroc Valley, N	Pahranagat Valley	Pahranagat Valley
FIELD STATION	<u> </u>	PA-1	PA-2	PA-3	PA-4	PA-5	PA-6
MAP NUMBER	2	1			1		

# FIELD OBSERVATIONS

TER (PERCENT)					CL	AST CO	UNT, >	% IN. T	0 ≤ 1	IN. DIA	METER	(PERC	ENT)		07:
DEL	ETERI	ous			NC	N-DEL	ETERIC	ous		DELETERIOUS			:	OTHER DELETERIOUS	
HERT	TUFF	GLASS	OTHER	.Qtz	Ls	Do	Gr	Vu	Vb	CALI- CHE	CHERT	TUFF	GLASS	OTHER	CLASTS PRESENT
			4	10	72	14		2		2					Chalcedony, Caliche
	6			2	20	60		2		16					Caliche
					62	34				4					Caliche
					76	24									Caliche
2					76	6				12	6				Caliche
2			6	2	60	30					4			4	Caliche

	SIZE D	ISTRIB	UTION				REMARKS	
OTHER LETERIOUS		NT OF	<3" %	GRADATION	MAXIMUM PARTICLE SIZE	PARTICLE SHAPE		
STS PRESENT	BOUL- DERS	COB- BLES			(CM)			
alcedony, liche					5	SA,SR	Surface	
liche	1	20			11	SA,SR	Stream Channel, Bottom	
liche					10	A,SA,SR	Shallow Wash	
liche					3	SA	Shallow Wash	
liche					4	SA,SR	Surface	
liche	0	20			10	SR,R	Road Cut	
			<u> </u> 					



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

SUMMARY OF FIELD PETROGRAPHIC AND GRAIN-SIZE ANALYSES PAHROC VALLEY, NEVADA

P JUN E

TABLE 8-1

PAGE 1 OF 1

APPENDIX C

# EXPLANATION OF TRENCH LOGS

Trench logs were completed for excavated trenches. Each log presented in this appendix is chosen from a group of trench logs so that it represents the general aggregate conditions and properties of that entire group. Occasionally, the full compliment of trenches in a group was not excavated due to low gravel percentages and/or advanced caliche development found in the first one or two trenches of that group. Detailed explanations of the trench logs headings are as follows:

# COLUMN HEADING

### **EXPLANATION**

BULK SAMPLE

Representative samples were obtained by channel sampling a trench wall. Overburden and, in some trenches, dense caliche layers were avoided during the sampling procedure.

- II 100 lb. sample (2 bags) for road-base
  aggregate testing.
- III 400 lb. sample (55 gallon barrel) for concrete aggregate testing.

DEPTH

Depth corresponds to depth below ground surface in meters and feet.

LITHOLOGY

Graphic representation of soil types present in excavation.

USCS

Unified Soil Classification System symbols. For detailed information see Table F-1.

CONSISTENCY

The consistency of the in-situ deposit was estimated by visual observation of the soil in the trench walls, ease (or difficulty) of excavation of the trench, and trench-wall stability.

Consistency descriptions of coarsegrained soils (GW, GP, GM, GC, SW, SP, SM, SC) are as follows:

# DESCRIPTION

Very Loose (VL)

Will not hold vertical cut (when dry).

Ertec

Loose (L)

Will hold vertical cut, but caves if disturbed.

Medium Dense (MD)

Holds vertical cut, even when disturbed; easily excavated.

Dense (D)

Holds vertical cut, difficult to excavate.

Very Dense (VD)

Very difficult to impossible to excavate.

SOIL DESCRIPTION

Except in cases where samples were classified based on laboratory data, the descriptions are based on visual classification. The procedures outlined in ASTM D 2487-69, Classification of Soils for Engineering Purposes and D 2488-69, Description of Soils (Visual-Manual Procedure) were followed. Solid lines across the column indicate known changes in the strata at the depth shown.

Definitions of some of the terms and criteria used to describe soils and conditions encountered during the excavation follow:

Descriptive Name

Name of soil, as determined by USCS, preceded by an adjective indicating the size range of the most abundant secondary material present.

Particle Size

For coarse-grained soils (sands and gravels) the size range of the particles visible to the unaided eye was estimated as fine, medium, coarse, or a combined range (e.g., fine to medium). These terms approximately correspond to the following sieve sizes:

Gravel Fine No. 4 to 3/4-inch sieve Coarse 3/4-inch to 3-inch sieve

Sand Fine No. 200 to No. 40 sieve Medium No. 40 to No. 10 sieve Coarse No. 10 to No. 4 sieve

Particle Shape

See Appendix B explanation pages.

Gradation

Gradations listed are those determined from percent amounts of boulders, cobbles, and gravel present. Descriptive terms used include: poor and well.

**E**ttec

Poor(ly)

Predominantly one size or a range of sizes, with some intermediate sizes missing.

Well

Wide range in grain sizes present, with substantial amounts of most intermediate sizes.

Secondary Material Percentage present by dry weight.

Trace 5-12 percent Little 13-20 percent Some > 20 percent

(e.g., Some slightly plastic silt)

Plasticity of Fines

See Appendix A explanation pages

HCL Reaction

As an aid for identifying calcium carbonate coatings and cementation, soil samples were tested in the field for their reaction to dilute hydrochloric acid. The intensity of the HCL reaction was described as none, weak, or strong.

Caliche

Caliche is a term applied to calcareous material of secondary accumulation. In this study, the definition includes both the soluble calcium (and other) salts and the clastic material (gravel, sand, silt or clay) in which the salts exist. See Table F-2 for a description of the stages of caliche development.

Cobbles and Boulders

See Appendix A explanation pages.

Lithology

The various rock types found in an excavated deposit are listed in order of decreasing abundance.

Remarks

This column was provided for comments regarding difficulty of excavation, caliche development, and backhoe refusal. Refusal indicates the inability of a JCB 3DIII backhoe (Case 680 equivalent) with a 2-foot wide bucket to excavate a trench to completion.

SIEVE ANALYSIS

The numbers cited represent the percentage by dry weight of each of the following soil components.

**E** Ertec

GR		aggregate particles that pass a
		(75 mm) sieve but are predomi-
	nantly sieve.	retained on a No. 4 (4.75 mm)

- SA Fine aggregate particles that almost entirely pass a No. 4 sieve but are predominantly retained on a No. 200 (0.075 mm) sieve.
- FI Soil particles that pass a No. 200 sieve (silt and clay).

All percentages shown on logs are the result of laboratory testing.

BULK SAMPLE	BULK SAMPLE METERS OF FEET T		LITHOLOGY	nscs	CONSISTENCY	SOIL DESCRIPTION	REMARKS	AN	IEV ALY	'SIS
	0	0		SM	medjum dense	SILTY SAND - OVERBURDEN				
	-1	2 - 4 -		GW	medium dense	SANDY GRAVEL, fine to coarse, subrounded, well graded; some fine to cease, subrounded send; strong HCI reaction; stage II cellishe from 3' to 4' and from 8.0' to 8.5'; some solubles and rare boulder; limestone/delemite, quartite, minor volcenies.		56	44	1
Ш		8 -	0,00.0		very dense		Refusel			
						TOTAL DEPTH 8.5 ft. (2.6m)				
	- 3	10 -								
	-4	12 -								
		14 -								
	-5	16 -								
		18 -								
	-6	20 -								

### TRENCH DETAILS

SURFACE ELEVATION : 4378 ft. (1338m)

DATE EXCAVATED : 30 October 1980

SURFACE GEOLOGIC UNIT : Adg

TRENCH LENGTH : 15 ft. (4.6m)

TRENCH ORIENTATION : NNE - SOW



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX

TRENCH LOG OF PA-A-1
PAHROC VALLEY, NEVADA

18 NUL 8

Figure C-1

BULK SAMPLE METERS D		PTH	LITHOLOGY	S	CONSISTENCY	COULDECORIOTION	DEMARKS	,	IEV ALY	
BULK S	METERS	FEET	ETTHOCOG!	SOSO	CONSIS	SOIL DESCRIPTION	REMARKS	L	GR SA FI	
	0	0		5M	loose	SILTY SAND - OVERBURDEN				
				SM	medium dense	SILTY SAND, stage II caliene throughout - OVER-BURDEN				
	-1	4-				SANDY GRAVEL, fine to coarse, subrounded, pearly graded; some fine to eacree, subrounded send; little slightly pleatic slit; strong HCI reaction; some stage II cellche; few cobbles; limestone/delomite, quartitie, minor valeanies.				
	- 2	6 -		GM	medjum dense					
	- 3	8 -			very dense		Refued			
		10 -				TOTAL DEPTH 10.0 ft. (3.0m)			Γ	Ī
	4	12 -								
		14 -								
	-5	16 -								
		18 -								
	-6	20 -								

### TRENCH DETAILS

SURFACE ELEVATION

: 4365 ft, (1330m)

DATE EXCAVATED

: 30 October 1980

SURFACE GEOLOGIC UNIT : Aufg

TRENCH LENGTH

: 14 ft. (4.3m)

" "NCH ORIENT! ION

: NNW - 98E



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX

TRENCH LOG OF PA-A-4 PAHROC VALLEY, NEVADA

White the second of the second

5 JUN 81

FIGURE C-2

BULK SAMPLE	METERS	FEET 🚽	LITHOLOGY	nscs	CONSISTENCY	SOIL DESCRIPTION	REMARKS		IEVI ALY	'SIS
	0	0		SM	loose	SILTY SAND - OVERBURDEN				
	-1	2 - 4 - 6 - 8 - 10 - 12 -		GP- GM	medium dense	SANDY GRAVEL, fine to coarse, subrounded, peorly graded; some fine to coarse, subrounded sand; trace slit; strong HCI reestion; trace stage I caliche; some cobbies, sare boulders; limestone, delomite, quartzite, minor chert.		64	31	5
	- 4	14 -				TOTAL DEPTH 13.0 ft. (4.0m)				
	-5	16 -								

### TRENCH DETAILS

SURFACE ELEVATION

: 4360 ft. (1329m)

DATE EXCAVATED

; 31 October 1980

SURFACE GEOLOGIC UNIT : Aufg

TRENCH LENGTH

; 15 ft. (4.6m)

TRENCH ORIENTATION : NNE - SEW



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE SMO/AFRCE-MX


TRENCH LOG OF PA-A-9 PAHRANAGAT VALLEY, NEVADA


5 JUN 81

FIGURE C-3

### APPENDIX D

FLOW DIAGRAM - ROAD-BASE AGGREGATES TESTING
FLOW DIAGRAM - CONCRETE TRIAL MIX DESIGN AND TESTING





### . APPENDIX E

CHEMICAL ANALYSES OF CEMENT, FLY ASH, AND WATER USED IN CONCRETE TRIAL MIXES

	PROPERTY ANALYZED	TOTAL PERCENTAGE OF SAMPLE	MINIMUM OR MAXIMUM REQUIREMENTS
	SiO <sub>2</sub>	26.8	20.0 MIN.
	AL <sub>2</sub> O <sub>3</sub>	1.96	6.0 MAX.
CEMENT ASTM C 150, TYPE II	Fe <sub>2</sub> O <sub>3</sub>	2.71	6.0 MAX.
ENT.	MgO	1.57	6.0 MAX.
CEMENT C 150, TN	ALKALIES (Na2O + 0.658 K2O)	0.53	0.60 MAX.
STM	LOSS ON IGNITION	0.56	3.0 MAX.
⋖	so <sub>3</sub>	1.97	3.0 MAX.
	INSOLUBLE RESIDUE	0.61	0.75 MAX.
	SiO <sub>2</sub>	67.7	-
	AL202	17.2	-
T.	Fe <sub>2</sub> O <sub>3</sub>	8.34	
H CLAS	TOTAL	93.24	70.0 MIN.
FLY ASH ASTM C 618, CLASS F	MgO	1.69	5.0 MAX.
F.	so <sub>3</sub>	0.14	5.0 MAX.
LSA AST	Ne <sub>2</sub> O (OPTIONAL)	1.68	1.5 MAX.
	MOISTURE	90.0	3,0 MAX.
	LOSS ON IGNITION	0.63	12.0 MAX.
Š	рН	7.5	-
WATER CALIF. DEPT. TRANS. SEC. 80 - 2.03	COLOR	0-5	_
WATER IF. DEPT. TR/ SEC. 90 - 2.03	so <sub>4</sub>	8 ppm	1300 ppm
F. D.	CI	10.6 ppm	650 ppm
₹ 5	OIL AND GREASE	NONE	NONE



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX

CHEMICAL ANALYSES OF CEMENT, FLY ASH, AND WATER USED IN CONCRETE TRIAL MIXES

S JUN 61

TABLE E-1

# APPENDIX F UNIFIED SOIL CLASSIFICATION SYSTEM SUMMARY OF CALICHE DEVELOPMENT ERTEC WESTERN GEOLOGIC UNIT CROSS REFERENCE

The state of the s

The state of the s

b

Above "A" like with P! between A mid 7 are benefities common requiring and of the property of Above "A" the with P! between 4 and 7 are burderlaw cases requiring use of duel symbols Not meeting all gradation requirements for G P Not meeting all gradation requirements for SP Congressing with at eased funcion limit in the funcion of the fun 3 Detween 1 and 3 Between f and 3 classification of fine grained Ormiter than 6 Oreater then 4 Asserbers Manies below
"A" Men 4.
Asserbers Manies above
"A" Men with FI
greater than 7 Atterberg limits below "A" line with PI greater than 7 Atterberg limits below
"A" line or Pi less than
5 Plasticity chart Laboratory Cleesification Criteria C. = 244 C. = 245 C. = 245 C. = 25 C. Cc = (Dr. 0 - 03 laboratory dref shappy

2% to 13%

Borderine cones the shappy

Work then 13%

Chi (Ch. 2h. 2h.

Work then cones tentuce of the stages the

School of the shappy

School of the shappy

Branding on becomere of these (traction me

School of the shappy

Branding on becomere of these (traction me **3 8 8** Pasticity index Give typical name; indicate appropriate provisions percentages of sand and grows; maximum sate; anglessing, select condition, and hardens of the course and hardens of the course and other perment and other perment and symbols in previous and symbols in Example:
Style amed, grevelly; about 20%
Shrif, amplate gravel pertectes
and subbanquier amed gravel
correct to fee, about 15% nonplastic flags with 15% nonstrength; well composited and
(SM) Give typical name; indicase degree and character of plantisty and carried and maximum tase of consett and maximum tase of consettions, debut if any local or problems and other parties and other parties and symbol in persentance. For undisturbed soils add informa-tion, or stratification, degree of compactness, commassion, mostlure conditions and d'himage cherniterstics Example: (Cayy 1811, brown; slightly plassie; small percentage of hire sand; sumerous vertical root botes; firm and dry in place; fosse; (ML) For undisturbed soils add infor-mation on structure, stratifica-tion, consistency is undisturbed and remouded states, motiture and drainage conditions Information Required for Describing Souts Incorpanie uits and very flore classy for sancts with sight of classy for sancts with sight of class and clays of leave to class and clays of leave to class, and clays, and clays, and clays, and clays. Organic uits and organic uits clays of few pleases of the measures o Silty grawth, poorly graded grawt-tand-till mintures Clayer gravels, poorly graded gravel-eaad-chy maxtures Poorly graded sands, gravelly sands, little or no frace graded Well preded gravels, gravel-tend mixtures, little or no fines Poorty graded gravels, gravel-sand mixiture, little or to fines Well graded sands, gravelly sands, hitle or no fines Silty sands, poorly graded sand-ailt mixtures Pest and other highly organic noise Clayey sands, poorly sand-clay mixtures Typical Name è Z N N 20 S ĭ S š 5 Ğ Š ಕ 3 5 Stages to Store Stages and stages and stages to stages to stage to Wide range in grain bines and substantial namemets of all intermediate particle since Phasic flues (for identification procedures, see C.L. below) Pleasin flues (for identification procedures, see CL below) Nomptentic flors (for identification pro-cadures, see Aff. Delow) Wide range in grain olds and substantial amounts of all insermediate particle sizes Prodomingally one size or a range of sizes with some intermediate sizes missing Nonplestic fame (for identification pro-coderes see Aff. below) Predominently one size or a range of sizes with some intermediate sizes missing Procedures on Praction Senatter than No. 40 Sieve Star Ĭ ž (Migutan Precedente 1 then 3 in. and basing fractions on 1 then weights) Distancy (reaction to stating) Orich to None to way ston Dry Strength (crucking cheracter-season) Nose 5 Pick Ment Highly Organic Soils Silis and clays isqued least greater than Oc Fine-grained toils in hold of meternal is amenty in ho. 360 sieve size of The No. 360 sieve Course-grained scale Mong these helf of material is kygus then No. 300 acus size

From Wagner, 1977.

Sandary, 1977.

Sandary, 1977.

Sandary, 1977.

Sandary, Sandarder, Sout personne characteristics of two prougs not blanch share as that chart are U.S. standard.

These presidents are to be performed on the minus No. 46 states has particles, plannary (Section 1) and particles of the performance of the perfor

The description of the control of th

Ertec

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE SMO/AFRCS-MX

UNIFIED SOIL CLASSIFICATION SYSTEM

TABLE F-1

### DIAGNOSTIC CARBONATE MORPHOLOGY

STAGE	GRAVELLY SOILS	NONGRAVELLY SOILS
I	Thin, discontinuous pebble coatings	Few filaments or faint coatings
п	Continuous pebble coatings, some interpebble fillings	Few to abundant nodules, flakes, filaments
ш	Many interpebble fillings	Many nodules and internodular fillings
Ħ	Laminar horizon overlying plugged horizon	Laminar horizon overlying plugged horizon

STAGE	I Weak Ca	II Strong Ca	M K	I <b>Y</b> Indurated K
GRAVELLY SOILS		0.00		K21m K22m K3
MONGRAVELLY SOILS				K2Im K22m K3

Stages of development of a cellabe profile with time. Stage I represents incipient carbonate assumulation, followed by continuous build-up of carbonate until, in Stage IV, the soil is completely plugged.

Reference: Gile, L.G. Poterson, F.F., and Grossman, R.B., 1985,

The K horizon: A master herizon of cerbenate essumulation: Sell Science, v. 96, p. 74-82.



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
SMO/AFRCE-MX

SUMMARY OF CALICHE DEVELOPEMENT

The second section is the second seco

8 JUN 81

TABLE E-3

### U ARSA POTENTIAL AGGREGATE SOURCE SYMBOLS

### ERTEC WESTERN GEOLOGIC UNIT UNIT EXPLANATION

	1001
	Segme in taginate major can in acquated, the ansatzy producing the property of the property of the party of the party in the state of the party of
	1 IMMENT (MMIFFERENTIATE) - Bacos (prope op parigeligation
GR	All a deline as geriphiny mainen mass  [1] Influence Telenica under formus de safrat- [1-20] And as delines maines imposite the Lightage
Vu	10 & grantin grandfreite dietite gabrei
	of inderentiate and stated company time formed by statistic formed and s
∨ь	2) Entimina - manic - Tolconic rotes at main comp- militar apprenty lotting by solid fighting at matter address; at an apprent and foot is g - manifest
Vu	1 Estiming (greatestic) - Mesha themed on occumential at researce pactor of one fail of them (et), aggression
Su	S DENTERTOR (METFECTURE TO THE DESCRIPTION OF ACCUMULATION AT CONTRACT SALIDS AND AT COMMISSION PRO- CIPITATED OCCUPATOR
Su, Qtz	S. Bronnings and in Stringing Repts. Complete it soop Sint garicide (4 g. andrison of themselving on ————————————————————————————————————
Ls, Do, Cau	So Carbonate Riccs - Composes programmanily or Carcina Carbonate percental or communication and participation or g
	Sa Brigh Lacobox Roses - Companies of cuts and rich-system  Marfaceles of gr. 6-741/adm plane constraint
	Su Empering Backs. Procreteror transmirely po- reparts of ambacklish of a market ground ambarto service.
Su	Sa Consta Constac Region Condition of grane incline or incline condition of condition of conditions
Mu	# METABLISHER . INDIFFERENTIATED . Reute formed through re- clystellitation in the toing state of presenting retail
Mu	bi nest and processe  (Course granue costs 'stone by higher-grade  (Course granue costs) or or the costs of processes  (Course granue costs of or or the course of processes
Mu Mu	By process granding contract of the contract o
Mu	
Qtz	the brokentaria racks throat by meconsciprion of highly self-cooper racks:
}	and the same of the
	A DESCRIPTION OFFICERY From to consequence unityrials separated principality by week water or gravity
Aai	Ai Touriga: Fluvist Sepakits - Major makers strans Channer and From-plain depokits
Au, Aad	(Ag Biddy Freeze) Reports   Biddy recred straps champl and freeze-base debasits to element (Access before ages maders derivation
Au	the Terran Repeats - Storm-from committe of taget officering as action characteristic files / St dauge Characteristic files /
Aol	An Propo and Locutering Supply Its - Supply Its - Supply Ing - It - Supply Ing - Its - Supply Its - It
Aaf	nctive pings at older last pods and obsessed shorarisms secondards sich getreet lasts (Au.)  As Alivest for Deposits: Atlanta (appents games) appents
	of deerny flow post potential alternal major approaches fronts grading nata productmently sold-initial alternate special control of the contr
Au	Sold proposed copposits comple to constant contractions  Sold proposed copposits comple proposity accordance units co
Ast	(fig. (fig.)) Provingers ones only two tensors of projecting
	met Am 1 Antenantier une emmissible fant somme au fent itent



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR PORCE
SMO/AFRCE-MX

ERTEC WESTERN GEOLOGIC UNIT CROSS REFERENCE

5 JUN 61

TABLE F-3

### APPENDIX G

CROSS REFERENCE FROM MAP NUMBER TO VERIFICATION ACTIVITY

### CROSS REFERENCE FROM MAP NUMBER TO VERIFICATION ACTIVITY

Included in this appendix is one table that is presented to allow cross reference to be made from this aggregate resources study to an appropriate verification study. Map numbers in the number series 400 to 599 on Drawing 1 are keyed to an in progress Verification report of Pahroc Valley, Nevada (E-TR-27-PA-I and II). If detailed information is required from a verification activity, the following search procedure can be used: determine the location of the activity required on Drawing 1, note the map number, refer to that map number in Table G-1, read from that table the verification activity type and number, refer to the appropriate verification report for the data required.

Table Number

Title

G-1

Cross Reference from Map Number to Verification Activity, Pahroc Valley, Nevada

MAP NUMBER	ACTIVITY LOCATION	MAP NUMBER	ACTIVITY LOCATION
401	GS - 30	423	CS · 12
402	T-3	424	GS - 22
463	G6 - 9	425	P-3
404	CS - 8	428	GS - 5
405	G\$ - 8	427	G6 - 21
406	T-4	428	G\$ - 32
407	GS - 28	429	CS - 13
406	G\$ - 27	430	GS - 4
409	T-6	431	T • 2
410	P-8	432	CS - 15
411	GS - 26	433	GS - 12
412	CS·3	434	G\$ - 7
413	GS - 3	436	P - 4
414	GS - 10	436	GS - 11
415	P-7	437	G <b>S</b> - 20
416	GS - 25	438	GS - 18
417	GS - 28	439	CS - 17
418	T-5	440	GS - 19
419	P - 6	441	GS - 8
420	GS - 24	442	P-2
421	G6 · 23	443	GS - 13
422	G8 - 31	444	GS - 14
-			

T - TRENCH

B - BORING

P - TEST PIT

CS - SURFACE SAMPLE

GS - GEOLOGIC STATION



MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX

CROSS REFERENCE FROM MAP NUMBER
TO VERIFICATION ACTIVITY
PAHROC VALLEY, NEVADA

8 JUN 81

TABLE 9-1 1 0F 2

MAP NUMBER	ACTIVITY LOCATION	MAP NUMBER	ACTIVITY LOCATION
445	G\$ - 17	467	GS - 48
446	CS - 19	466	G <b>6</b> · 44
447	<b>68</b> - 16	469	GS · 40
448	P-1	470	G6 - 43
449	T-1	471	GS - 37
459	G <b>6</b> - 15	472	GS - 41
461	GS -1	473	GS · 42
452	P - 12	474	GS - 38
453	GS · 2	475	GS - 33
454	G\$ · 47		
485	G5 - 34		
456	GS - 40		
457	CS · 23		
458	G6 · 46		
459	GS - 45		
400	P-9		
461	GS - 39	}	Ì
462	CS - 25	1	
463	G6 - 36		
464	P · 10	1	
405	GS - 36		
406	CS - 27		}

T - TRENCH

B - BORING

P - TEST PIT

CS - SURFACE SAMPLE

**GS - GEOLOGIC STATION** 





MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE BMO/AFRCE-MX


CROSS REFERENCE FROM MAP NUMBER TO VERIFICATION ACTIVITY PAHROC VALLEY, NEVADA


8 JUN 81


TABLE 6-1 2 0F 2
















### EXPL

### EHTEC WESTERN AGGREGATE RESOURCES STUDY FIELD STATIONS

# VALLEY SPECIFIC AGGREGATE RESOURCES STUDY (MAP NUMBERS FROM 1 TO 199)

### BASIN: FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- DATA STOP, SAMPLED AND TESTED
- O DATA STOP

### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

- ▲ DATA STOP, SAMPLED AND TESTED
- **A DATA STOP**

### DETAILED AGGREGATE RESOURCES STUDY \*\*

(MAP NUMBERS FROM 200 TO 299 FOR BASIN-FILL AND ROCK SAMPLE LOCATIONS; 300 TO 399 FOR FIELD PETROGRAPHIC STATIONS)

### BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- DATA STOP, SAMPLED AND TESTED
- o DATA STOP

### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

▲ DATA STOP, SAMPLED AND TESTED

### PETROGRAPHIC FIELD STATIONS

DATA STOP

### ANATION

# EXISTING ERTEC WESTERN TEST DATA LOCATIONS \*\*\* (MAP NUMBERS FROM 400 TO 599)

- DATA STOP, SAMPLED AND TESTED
- DATA STOP
- \* SEE DRY LAKE, MULESHOE, DELAMAR, PAHROC VSARS REPORT (FN-TR-37-a) FOR DETAILED INFORMATION.
- \* \* SEE CORRESPONDING MAP NUMBER IN APPENDICES A AND B FOR DETAILED INFORMATION.
- \* \* \* SEE CORRESPONDING MAP NUMBER AND ACTIVITY TYPE IN APPENDIX G FOR REFERENCE TO THE IN PROGRESS PAHROC VALLEY VERIFICATION REPORT (E-TR-27-PA-I AND II).

### SYMBOLS


STUDY AREA BOUNDARY

ROCK/BASIN-FILL CONTACT




NORTH

SCALE 1:62,500



**LOCATION MAP** 



C VSARS TION.

DICES A AND B

VITY TYPE IN RESS PAHROC AND II).




MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX


FIELD STATION AND SELECTED
EXISTING DATA SITE LOCATIONS
DETAILED AGGREGATE RESOURCES STUDY
PAHROC STUDY AREA, NEVADA


5 JUN 81


**DRAWING 1** 
















### ERTEC WESTERN AGGREGATE RESOURCES STUDY FIELD STATIONS

VALLEY-SPECIFIC AGGREGATE RESOURCES STUDY \* (MAP NUMBERS FROM 1 TO 199)

### BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- DATA STOP, SAMPLED AND TESTED
- o DATA STOP

### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

- ▲ DATA STOP, SAMPLED AND TESTED
- Δ DATA STOP

### DETAILED AGGREGATE RESOURCES STUDY \* \*

(MAP NUMBERS FROM 200 TO 299 FOR BASIN-FILL AND ROCK SAMPLE LOCATIONS; 300 TO 399 FOR FIELD PETROGRAPHIC STATIONS)

### . BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

DATA STOP, SAMPLED AND TESTED

BATA STOP

DARIN-FIL

Res


005-

RBII

115,000

# **EXPLANATION**

	AGGREGA	GEOLOGIC UNITS	
AN	ND ROCK SOURCES		BA
	BASIN FILL ROCK	BASIN-FILL OR ROCK SOURCES CONTAINING MATERIALS SUITABLE FOR USE AS ROAD-BASE AGGRE- GATES; BASED ON ACCEPTABLE LABORATORY AGGRE- GATE TEST RESULTS.	Aaf Al
ô.	BASIN FILL	BASIN-FILL SOURCES CONTAINING MATERIALS SUITABLE FOR USE AS ROAD-BASE AGGREGATES; BASED ON CORRELATION WITH CLASS RBIB SOURCE AREAS.	Do Di
		POYENTIAL BASIN-FILL SOURCES OF MATERIALS	† SEE APPENDIX TABLE
	BASIN FILL	SUITABLE FOR USE AS ROAD-BASE AGGREGATES; BASED ON PHOTOGEOLOGIC INTERPRETATIONS, FIELD OBSERVATIONS, AND LIMITED OR INCONCLUSIVE SIEVE ANALYSIS AND/OR ABRASION DATA.	SYMBOLS **
		UNSUITABLE SOURCES OF BASIN-FILL MATERIALS	
		THAT MAY LOCALLY CONTAIN POTENTIALLY SUIT- ABLE SOURCES OF AGGREGATES OF LIMITED EXTENT.	
		UNTESTED SOURCES OF ROCK MATERIALS THAT MAY CONTAIN POTENTIALLY SUITABLE CRUSHED-ROCK AGGREGATES (SEE TEXT FOR ADDITIONAL INFORMATION).	
	Q		
PL -E		ION SYSTEM IS SHOWN, ALTHOUGH ALL RCES MAY NOT BE PRESENT WITHIN	tt GEOLOGIC ROCK APPROXIMATELY





LUVIAL FAN DEPOSITS

(A5)

OCK UNITS

DLOMITE ROCKS

**(S2)** 

F-3 FOR SYMBOL EXPLANATION AND COMPARISON

TUDY AREA BOUNDARY


POCK/BASIN-FILL CONTACT

GEOLOGIC ROCK CONTACT


BASIN-FILL CONTACT



SCALE 1:62,500



LOCATION MAP



-- SUL CONTACTS ARE

### ERTEC WESTERN AGGREGATE RESCURCES TO A STATE OF THE STATE

### VALLEY-SPECIFIC AGGREGATE RESOURCES STUDY \* (MAP NUMBERS FROM 1 TO 199)

#### BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- DATA STOP, SAMPLED AND TESTED
- o DATA STOP

### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

- ▲ DATA STOP, SAMPLED AND TESTED
- **DATA STOP**

### DETAILED AGGREGATE RESOURCES STUDY \* \*

(MAP NUMBERS FROM 200 TO 299 FOR BASIN-FILL AND ROCK SAMPLE LOCATIONS; 300 TO 399 FOR FIELD PETROGRAPHIC STATIONS)

#### BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- DATA STOP, SAMPLED AND TESTED
- O DATA STOP

### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

▲ DATA STOP, SAMPLED AND TESTED

### PETROGRAPHIC FIELD STATIONS

- DATA STOP
- \* SEE DRY LAKE, MULESHOE, DELAMAR, PAHROC VSARS REPORT (FN-TR-37-a) FOR DETAILED INFORMATION.
- \* \* SEE CORRESPONDING MAP NUMBER IN APPENDICES A AND B FOR DETAILED INFORMATION.

### AGGREGATE CLASSIFICATION SYSTEM

### BASIN-FILL AND ROCK SOURCES \* \* \*

BASIN-FILL OR ROCK SOURCES CONTAINING **BASIN FILL** MATERIALS SUITABLE FOR USE AS ROAD-BASE AGGRE-**RBIa** GATES; BASED ON ACCEPTABLE LABORATORY AGGRE-ROCK **GATE TEST RESULTS.** BASIN-FILL SOURCES CONTAINING MATERIALS SUITABLE FOR USE AS ROAD-BASE AGGREGATES; **BASIN FILL** BASED ON CORRELATION WITH CLASS RBIA SOURCE RBIb AREAS. POTENTIAL BASIN-FILL SOURCES OF MATERIALS SUITABLE FOR USE AS ROAD-BASE AGGREGATES; BASED ON PHOTOGEOLOGIC INTERPRETATIONS, FIELD **BASIN FILL** RBII OBSERVATIONS, AND LIMITED OR INCONCLUSIVE SIEVE ANALYSIS AND/OR ABRASION DATA. UNSUITABLE SOURCES OF BASIN-FILL MATERIALS THAT MAY LOCALLY CONTAIN POTENTIALLY SUIT-ABLE SOURCES OF AGGREGATES OF LIMITED EXTENT. UNTESTED SOURCES OF ROCK MATERIALS THAT MAY CONTAIN POTENTIALLY SUITABLE CRUSHED-ROCK AGGREGATES (SEE TEXT FOR ADDITIONAL INFORMA-TION).


\* \* A COMPLETE CLASSIFICATION SYSTEM IS SHOWN, ALTHOUGH ALL BASIN-FILL OR ROCK SOURCES MAY NOT BE PRESENT WITHIN THE STUDY AREA.

GEOLOGIC UNITE				
	BASIN-FILL UNITS			
Aaf	ALLUVIAL FAN DEPOSITS	(A5)	9. 0	
	ROCK UNITS		si o	
Do	DOLOMITE ROCKS	(52)	LQ	
T SEE APPENDIX T	TABLE F-3 FOR SYMBOL EXPLANATION AN	D COMPARISON	NEVA	
	STUDY AREA BOUNDARY			
	ROCK/BASIN-FILL CONTACT		MAP AREA	
-	GEOLOGIC ROCK CONTACT			
	BASIN-FILL CONTACT			
GEOLOGIC ROCK AND BASIN-FILL CONTACTS ARE APPROXIMATELY LOCATED AND MAY VARY LOCALLY.				

**E**Ertec

ROAD-BASE A
DETAILED AGE
PAHROC

5 JUN 81






MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX


ROAD-BASE AGGREGATE RESOURCES MAP DETAILED AGGREGATE RESOURCES STUDY PAHROC STUDY AREA, NEVADA


5 JUN 81


DRAWING 2

















#### REGATE RESOURCES STUDY FIELD STATIONS

FIC AGGREGATE RESOURCES STUDY \*

MBERS FROM 1 TO 199)

MLL UNITS (COARSE AND/OR FINE AGGREGATES)

DATA STOP, SAMPLED AND TESTED

DATA STOP

MTS (CRUSHED-ROCK AGGREGATES)

DATA STOP, SAMPLED AND TESTED

DATA STOP

#### REGATE RESOURCES STUDY • •

MBERS FROM 200 TO 290 FOR BASIN—FILL X BAMPLE LOCATIONS; 300 TO 399 LD PÉTROGRAPHIC STATIONS!

MLL UNITS (COARSE AND/OR FINE AGGREGATES)

DATA STOP, SAMPLED AND TESTED

## AGGREGATE CLASSIFICATION SYSTEM \*\*\*

#### **BASIN-FILL AND ROCK SOURCES**

CA1

BASIN FILL

ROCK

BASIN-FILL OR RO AGGREGATES THA CONCRETE WITH 2 STRENGTHS EQUA

6500 PSI.

CA2



BASIN FILL

ROCK

BASIN-FILL OR RO AGGREGATES THA CONCRETE WITH: STRENGTHS LESS T

СВ



BASIN FILL

ROCK

BASIN-FILL OR RC AGGREGATES POT IN CONCRETE; BAS TORY AGGREGAT

CC1



**BASIN FILL** 

ROCK

BASIN—FILL OR RI AGGREGATES POT IN CONCRETE; BAS CLASS CA1 OR CA2

CC2




BASIN FILL

Basin—fill sour Potentially suc Based on corre Areas.

# **EXPLANATION**

## GEOLOGIC UNITS


		BASIN-FILL UNITS		
K SOURCER CONTAINING PRODUCED TRIAL MIX DAY COMPRESSIVE TO OR GREATER THAN	Aaf	ALLUVIAL FAN DEPOSITS		
K ROURGER CONTAINING		ROCK UNITS		
PRODUCED TRIAL MIX DAY COMPRESSIVE IAN 8500 PSI.	Do	DOLOMITE ROCKS		
M BOURCES CONTAINING WILLY SUITABLE FOR USE	Cau	CARBONATE ROCKS UNDIFFERENTIATED		
D ON ACCEPTABLE LABORA- FRAT RESULTS.	† SEE APPENDIX TABLE F-3 FOR SYMBOL EXPLANATION AND CO			
K Sources containing FTIALLY SUITABLE FOR USE DON CORRELATION WIT. BURGE AREAS.	SYMBOLS 11			
		STUDY AREA BOUNDARY		
CONTAINING AUGREGATES LE FOR USE IN CONCRETE; LON WITH CLASS CO SOURCE		ROCK/BASIN-FILL CONTACT		
0	-	GROVOGIC BOCK CONTROLS		





. NORTH.

SCALE 1:62,500



(S2)

(A5)

NOIFFERENTIATED (S2)

LANATION AND COMPARISON.

NEVADA UTAH
MAP AREA

12.

NTACT

## VALLEY-SPECIFIC AGGREGATE RESOURCES STUDY \* (MAP NUMBERS FROM 1 TO 199)

## BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- . DATA STOP, SAMPLED AND TESTED
- O DATA STOP

#### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

- ▲ DATA STOP, SAMPLED AND TESTED
- △ DATA STOF

## **DETAILED AGGREGATE RESOURCES STUDY \* \***

(MAP NUMBERS FROM 200 TO 299 FOR BASIN-FILL AND ROCK SAMPLE LOCATIONS; 300 TO 399 FOR FIELD PETROGRAPHIC STATIONS!

### BASIN-FILL UNITS (COARSE AND/OR FINE AGGREGATES)

- DATA STOP, SAMPLED AND TESTED
- O DATA STOP

#### **ROCK UNITS (CRUSHED-ROCK AGGREGATES)**

▲ DATA STOP, SAMPLED AND TESTED

#### PETROGRAPHIC FIELD STATIONS

- DATA STOP
- \* SEE DRY LAKE, MULESHOE, DELAMAR, PAHROC VSARS REPORT (FN-TR-37-4) FOR DETAILED INFORMATION.
- \* " SES CORRESPONDING MAP NUMBER IN APPENDICES A AND B FORESTARLED INFORMATION.

## BASIN-FILL AND ROCK SOURCES

CA1	BASIN FILL ROCK	BASIN—FILL OR ROCK SOURCES CONTAINING AGGREGATES THAT PRODUCED TRIAL MIX CONCRETE WITH 28-03-7 COMPRESSIVE STRENGTHS EQUAL TO OR GREATER THAN 6500 PSI.
CA2	BASIN FILL ROCK	BASIN-FILL OR ROCK SOURCES CONTAINING AGGREGATES THAT PRODUCED TRIAL MIX CONCRETE WITH 28-DAY COMPRESSIVE STRENGTHS LESS THAN 6500 PSI.
CB	BASIN FILL ROCK	BASIN-FILL OR ROCK SOURCES CONTAINING AGGREGATES POTENTIALLY SUITABLE FOR USE IN CONCRETE; BASED ON ACCEPTABLE LABORATORY AGGREGATE TEST RESULTS.
CC1	BASIN FILL ROCK	BASIN—FILL OR ROCK SOURCES CONTAINING AGGREGATES POTENTIALLY SUITABLE FOR USE IN CONCRETE; BASED ON CORRELATION WITH CLASS CA1 OR CA2 SOURCE AREAS.
CC2	BASIN FILL	BASIN—FILL SOURCES CONTAINING AGGREGATES POTENTIALLY SUITABLE FOR USE IN CONCRETE; BASED ON CORRELATION WITH CLASS CB SOURCE AREAS.
		BASIN-FILL SOURCES CONTAINING FINE AGGREGATES USED WITH CRUSHED-ROCK SAMPLES FOR CERTAIN CONCRETE TRIAL MIXES.
		UNSUITABLE SOURCES OF BASIN-FILL MATERIALS THAT MAY LOCALLY CONTAIN POTENTIALLY SUIT- ABLE SOURCES OF AGGREGATES OF LIMITED EXTENT. UNTESTED SOURCES OF ROCK MATERIALS THAT: MAY: CONTAIN POTENTIALLY SUITABLE CRUSHED-ROCK AGGREGATES (SEE TEXT FOR ADDITIONAL INFORMATION).

SYME

<sup>• • •</sup> A COMPLETE CLASSIFICATION SYSTEM IS SHOWN, ALTHOUGH ALL BASIN -FILL OR ROCK SOURCES MAY NOT BE PRESENT WITHIN THE STUDY AREA.

	70 Management of the Control of the		
	BASIN-FILL UNITS		SCALE 1
Aaf	ALLUVIAL FAN DEPOSITS	(A5)	0 1
	ROCK UNITS		STATUTE 0 1 KILOME
Do	DOLOMITE ROCKS	(S2)	
Cau	CARBONATE ROCKS UNDIFFERENTIATED	(\$2)	LOCATIO
see appendix t	ABLE F-3 FOR SYMBOL EXPLANATION AND COMPA		NEVADA
YMBOLS 11	CTUDY AREA DOUBLE AND		MAP AREA
	STUDY AREA BOUNDARY  ROCK/BASIN-FILL CONTACT		
	GEOLOGIC ROCK CONTACT	9	
	BASIN-FILL CONTACT		
ARE APPROX	OCK AND BARN-FILL CONTACTS WHATELY LOCATED AND MAY		•
VARY LOCAL	±L.▼.		=Ector
			: <b></b>




CONCRETE AGGRED
DETAILED AGGRED
PAHROC ST

5JUN 81

10 :11

SCALE 1:62,500

(A5)




**(S2)** 

132

FERENTIATED

**(S2)** 

MATION AND COMPARISON.



ACT

ET

4

CTS



MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE
BMO/AFRCE-MX

CONCRETE AGGREGATE RESOURCES MAP DETAILED AGGREGATE RESOURCES STUDY PAHROC STUDY AREA, NEVADA

5 JUN 81

DRAWING 3